

tional Library Bibliothèque nationale Canada du Canada

Canadian Theses Service

Service des thèses canadiennes

Ottawa, Canada K1A 0N4

## NOTICE

The quality of this microform is heavily dependent upon the quality of the original thesis submitted for microfilming. Every effort has been made to ensure the highest quality of reproduction possible.

If pages are missing, contact the university which granted the degree.

Some pages may have indistinct print especially if the original pages were typed with a poor typewriter ribbon or if the university sent us an inferior photocopy.

Reproduction in full or in part of this microform is governed by the Canadian Copyright Act, R.S.C. 1970, c. C-30, and subsequent amendments.

# **AVIS**

La qualité de cette microforme dépend grandement de la qualité de la thèse soumise au microfilmage. Nous avons tout fait pour assurer une qualité supérieure de reproduction.

S'il manque des pages, veuillez communiquer avec l'université qui a conféré le grade.

La qualité d'impression de certaines pages peut laisser à désirer, surtout si les pages originales ont été dactylographiées à l'aide d'un ruban usé ou si l'université nous a fait parvenir une photocopie de qualité inférieure.

La reproduction, même partielle, de cette microforme est soumise à la Loi canadienne sur le droit d'auteur, SRC 1970, c. C-30, et ses amendements subséquents.



Variation in the Behavior of Humpback Whales: A study of Individuals

by

Carole Anne Carlson

Submitted in partial fullfillment of the requirements for the degree of Doctor of Philosophy

at

Dalhousie University Halifax, Nova Scotia January, 1992

(C) Copyright by Carole Anne Carlson, 1992



National Library of Canada

Bibliothèque nationale du Canada

Canadian Theses Service

Service des thèses canadiennes

Ottawa, Canada K1A ON4

> The author has granted an irrevocable nonexclusive licence allowing the National Library of Canada to reproduce, loan, distribute or sell copies of his/her thesis by any means and in any form or format, making this thesis available to interested persons.

> The author retains ownership of the copyright in his/her thesis. Neither the mesis nor substantial extracts from it may be printed or otherwise reproduced without his/her permission.

L'auteur a accordé une licence irrévocable et non exclusive permettant à la Bibliothèque nationale du Canada de reproduire, prêter, distribuer ou venure des coples de sa thèse de quelque manière et sous quelque forme que ce soit pour mettre des exemplaires de cette thèse à la disposition des personnes intéressées.

L'auteur conserve la propriété du droit d'auteur qui protège sa thèse. Ni la thèse ni des extraits substantiels de celle-ci ne doivent être imprimés ou autrement reproduits sans son autorisation.

ISBN 0-315-76687-5

Canadä

# DALHOUSIE UNIVERSITY FACULTY OF GRADUATE STUDIES

The undersigned hereby certify that they have read and
recommend to the Faculty of Graduate Studies for acceptance a
thesis entitled: " Variation in the Behavior of Humpback
Whales: A Study of Individuals"
by Carole Anne Carlson
in partial fulfillment of the requirements for the degree of Doctor
of Philosophy.

External Examiner
Research Supervisor
Examining Committee

Dated 4/3/4

#### DALHOUSIE UNIVERSITY

Date: April 1992

AUTHOR: Carole A. Carlson

TITLE: Variation in the Behavior of Humpback Whales:

A Study of Individuals

DEPARTMENT OR SCHOOL: Dalhousie University

DEGREE: PhD CONVOCATION: May YEAR: 1992

Permission is herewith granted to Dalhousie University to circulate and to have copied for non-commercial purposes, at its discretion, the above title upon the request of individuals or institutions.

Signature of Author

THE AUTHOR RESERVES OTHER PUBLICATION RIGHTS, AND NEITHER THE THESIS NOR EXTRACTS FROM IT MAY BE PRINTED OR OTHERWISE REPRODUCED WITHOUT THE AUTHOR'S WRITTEN PERMISSION.

THE AUTHOR ATTESTS THAT PERMISSION HAS BEEN OBTAINED FOR THE USE OF ANY COPYRIGHTED MATERIAL APPEARING IN THIS THESIS (OTHER THAN BRIEF EXCERPTS REQUIRING ONLY PROPER ACKNOWLEDGEMENT IN SCHOLARLY WRITING) AND THAT ALL SUCH USE IS CLEARLY ACKNOWLEDGED.

# TABLE OF CONTENTS

<u>Page</u>
List of Figuresvii
List of Tables ix
ABSTRACT xi
Acknowledgementsxii
CHAPTER 1. INTRODUCTION 1
1.1. The humpback whale: Natural history 1
1.1.1. Humpback whales of the western North
Atlantic 6
1.2. Comparative studies 7
1.2.1. Interspecific comparisons 7
1.2.2. Intraspecific or interindividual
comparisons 10
1.2.3. Studies of individuals 11
CHAPTER 2. METHODS
2.1. The study area 17
2.2. Whalewatching and research cruises 17
2.3. Data collection 19
2.4. Photographic equipment and film 21
2.5. Identification of individual whales 21
2.6. Analysis of photographs 22
2 7 Database 22

<u>Page</u>	<u>e</u>
2.7.1 Data entry and selection of individ-	
ual whales 2	3
2.8. Behavioral measures 2	4
2.9. Statistical analyses 2	7
2.9.1. Relationship between gender and	
fluke coloration and scarification 3	3
2.9.2. General behavioral correlations3	3
2.9.3. Variation in behavior3	4
CHAPTER 3. RESULTS 3	6
3.1. Fluke coloration and scarification 3	6
3.2. General behavioral correlations 3	8
3.3. Variation in behavior with age-class 4	4
3.4. Variation in behavior with age 5	1
3.5. Variation in behavior with gender 5	5
3.6. Variation in behavior with reproductive	
status 5	59
3.7. Variation by year	53
3.8. Variation in behavior by individual	57
3.9. General highlights of results	71
CHAPTER 4. DISCUSSION	73
4.1. Humpback whale behavior	73
4.1.1. Near-boat behavior	73
4.1.2. Breaching, flippering and lobtailing.	78

			<u>Pa</u>	ide
	4.1.3.	Feeding	• •	80
	4.1.4.	Spyhopping		82
	4.1.5.	Low respiration or resting	••	83
	4.1.6.	Sociality/Mean group size	• •	85
	4.1.7.	Arrival, departure and residency		90
	4.1.8.	Relative distance	••	94
4.2.	Indivi	dual differences in behavior	••	98
4.3.	Between	n-year differences in behavior	:	101
	4.3.1.	Sandlance abundance	. <b></b> :	101
	4.3.2.	Whale abundance	:	103
CONCLUSIO	NS		:	104
APPENDIX	ı		:	105
APPENDIX	II		• • •	117
	c			119

## LIST OF FIGURES

<u>Figur</u>	<u>res</u>	<u>Paqe</u>
1.0.	A breaching humpback whale	. 2
2.1.	The study area	. 18
2.2.	Descriptions and photographs of breaching behavior near-boat behavior, lobtailing behavior and low respiration events (resting)	
2.3.	Descriptions and photographs of lunge feeding behavior and flippering behavior	. 29
2.4.	Descriptions and photographs of lobtailing behavior and spyhopping behavior	. 30
2.5.	Categories of fluke coloration	. 32
3.1.	Box plots of rates of near-boat behavior, breachi behavior, lobtailing behavior and spyhopping behavior by age-class	_
3.2.	Box plots of rates of resting behavior, surface feeding behavior, sociality and mean group size by age-class	. 47
3.3.	Box plots of rates of departure, residency and relative distance by age-class	. 48
3.4.	Sociality, mean group size, rates of resting behavior and surface feeding behavior plotted by age	. 53
3.5.	Box plots of rates of surface feeding behavior, sociality, gender, and arrival by gender	57
3.6.	Box plots of rates of sociality, mean group size, arrival and departure by reproductive status	. 61

<u>Figur</u>	<u>res</u>	<u>Page</u>
3.7.	Rates of spyhopping behavior, breaching behavior, lobtailing behavior, flippering behavior, resting behavior and surface feeding behavior plotted by year	65
3.8.	Rates of near-boat behavior, sociality, arrival, departure, residency and relative distance plotted by year	66

# LIST OF TABLES

<u>Table</u>	<u>Page</u>
2.1. Number of cruises, length of field season, and number of individual humpback whales observed between 1979 and 1985	20
2.2. Number of individual whales in study summarized by sex, reproductive status and age	31
3.1. Fluke coloration (as shown in Figure 4) listed by gender	37
3.2. Principal Component Analysis: component loadings and eigenvalues for those components with eigenvalues greater than 1.0	40
3.3. Matrix of Spearman Correlation coefficients incluing sandlance abundance and whale abundance	
3.4. Matrix of Spearman Correlation coefficients for juveniles, including sandlance abundance and whale abundance	42
3.5. Matrix of Spearman Correlation coefficients for adults, including sandlance abundance and whale abundance	43
3.6. Natural logs of mean scores for behavior by age- class with Kruskall-Wallis test statistics	45
3.7. Two-way Analysis of Variance test statistics for behavior by age-class by year	50
3.8. Natural logs of mean scores for behavior by age with Kruskal-Wallis test statistics	52
3.9. Two-way Analysis of Variance test statistics for behavior by age, by year	
3.10.Natural logs of mean scores for behavior by gende with Mann-Whitney U test statistics	

<u>Table</u>		<u>Page</u>
3.11.	Two-way Analysis of Variance test statistic for behavior by age, by year	58
3.12.	Natural logs of mean scores for behavior by gender with Mann-Whitney U test statistics	
3.13.	Two-way Analysis of Vatiance test statistics for behavior by reproductive status, by year	62
3.14.	Natural logs of mean scores for behavior by year with Kruskal-Wallis test statistics	64
3.15.	Friedman Two-way Analysis of Variance test statistics for behavior by individual, bt year	68
3.16.	Two-way Analysis of Variance test statistics for behavior by individual female, by year	
3.17.	Two-way Analysis of Variance test statistics for behavior by individual male, by year	

#### ABSTRACT

Variation in the behavior of individuals within a seasonally returning population of humpback whales on Stellwagen Bank, Massachusetts, was studied using data collected between 1979 and 1985. The data presented were derived from observations aboard 30m commercial whalewatching vessels and dedicated cruises aboard a 12m research vessel. Possible relationships between behavioral measures and sex, age-class and reproductive status were examined.

Individual whales were photographically identified by natural markings on the ventral surface of the flukes as well as dorsal fin shape and prominant scarification. One hundred and twenty-seven individual humpback whales of known gender, that had been observed for more than one year, were chosen for the study.

Results of statistical analyses indicate that although there are few strong behavioral correlations between individuals, individual whales may be arranged in a rough continuum ranging from social to less social individuals.

The most significant differences in behavior between classes of whales were found between juveniles and adults. Juvenile whales generally approach boats, lobtail, breach, spyhop, flipper and rest more than adults, who are more social, feed more frequently and tend to be a greater distance from the centroid of whale distribution. There are significant relationships between age and sociality, mean group size and resting behaviors. Rates of resting were greater in younger whales while sociality generally increased with age.

Significant differences were found between gender and rates of feeding, sociality and arrival time with males generally feeding more frequently and arriving later than females. Females were generally more social. Pregnant and lactating females differed significantly in rates of arrival time, departure time, mean group size and sociality.

Statistical analyses indicate significant differences between individuals for near-boat, breaching and feeding events, time of residence, mean group size and sociality. Individual females tend to vary their behavior more than males, except for boat approaches and arrival time.

The behavioral events examined are reviewed and their possible function(s) discussed in the context of the new data presented.

#### ACKNOWLEDGEMENTS

Thirteen years ago I was first introduced to the life on and in the waters near Stellwagen Bank. Since that time, I have met, worked with, learned from and been inspired by many. The work itself is a collaboration of efforts and I am indebted to many colleagues and friends, for without their help, this study would not have been possible.

I am most grateful for the support, guidance and friendship of my advisor, Dr. Hal Whitehead. He generously gave his time and shared his expertise in statistics and behavioral ecology. His careful critique of the many manuscripts and his insights into behavioral studies were invaluable to my work.

My fellow graduate students Annick Faucher, Antonio Abboud, Dr. Lindy Weilgart, Monica Muelbert and Marcos Alvarez provided encouragement and ideas as did Dr. Leo Vining who believed that "independent researchers" were worth supporting. My friend Susan Waters generously shared her time, expertise and home.

The members of my committee, Drs. Robert Scheibling, John Fentress and Ian McLaren encouraged me and provided very careful, helpful comments on this thesis. Dr. Howard Winn from the University of Rhode Island also provided a most insightful review.

Dr. John Jahoda of Bridgewater State College, Mason Weinrich and colleagues of CRU and Carl Haycock of BIOS shared ideas and data and offered suggestions for this work. Howard and Candy Garrett provided graphics, Sue Oliver helped with analysis and Ned Oliver with collation during those final, frantic hours. Jean Frottier generously offered the use of his computer and printer, and Tom and Janet Reinhart provided me with a peaceful place to live and work.

This study was initiated, and continues, at the Center for Coastal Studies in Provincetown. I am greatly indebted to Dr. Charles "Stormy" Mayo III for enlisting me as a member of his research team in 1979 and introducing me to the world of whales and plankton. Sharon Pittman, David Mattila, Phil Clapham and Marilyn Marx greatly helped with the data management and extraction of data. Jean Kenyon, Dr. Graham Geise and Charlie Wescott provided continual encouragement.

The majority of the data used for this study was collected aboard the Dolphin Fleet whale watching vessels of Provincetown, Massachusetts. I am indebted to their captains and crew for their help and expertise and to a host of volunteer data collectors for their assistance.

I am extremely grateful and thankful for my parents, Sophie and Angelo, who have provided continual support and encouragement over the years, as well as to a strong network of women friends in Provincetown.

This work was funded in part by the American Museum of Natural History, Cetacean Society International, International Wildlife Coalition, National Marine Fisheries Service and the Center for Coastal Studies.

Drs. George Nichols, Michael Bigg and Barbara Mayo inspired much of my work, while Talon, Beltane, Pegasus, Comet, Silver and many others made it more than enjoyable. It is to their memory that this thesis is dedicated.

# CHAPTER 1. INTRODUCTION

The purpose of this study is to examine the variation in behavior of individuals within a seasonally returning population of humpback whales that visited Stellwagen Bank, Massachusetts during 1979-1985 and to investigate possible relationships between behavior and sex, age-class and reproductive status.

# 1.1 The humpback whale: Natural history

Once I saw a whale
With "sentimental indian eyes"
And flippers as white as
snow

And barnacles all over his belly

And his baleen thin as

And his nose like a pickle
SEAN WONDER, AGE 7

The humpback whale, <u>Megaptera novaeangliae</u> (Figure 1.0), a member of the family Balaenopteridae, exists in all oceans of the world. Humpbacks are usually found in temperate, productive waters during the summer months and winter in




Figure 1.0. A breaching humpback whale.

tropical or sub-tropical waters (Matthews, 1937; Mackintosh, 1965). This migration relates to the life cycle of the species, as they feed during the summer and breed and calve during the winter months (Chittleborough, 1958; Matthews, 1937; Mackintosh, 1942). The gestation period is approximately twelve months and the most common breeding cycle results in one calf every two years, although successful post-partum ovulation in some females may result in two calves in two years (Chittleborough, 1958).

Like most baleen whales, humpback whales do not appear to group closely together. Most sightings are of single or two animals (Wolman and Jurasz, 1977; Mayo, 1982; Whitehead, 1983) and rarely exceed four or five (Evans, 1987) unless breeding or feeding aggregations are observed. Although little is known about the exact social structure of the humpback, group dynamics on low-latitude breeding grounds appear to be quite complex (Herman and Antinoja, 1977; Tyack and Whitehead, 1983; Mattila et al., 1985). Few long-term associations have been observed on high-latitude feeding grounds, except those noted by Baker et al. (1986) and Weinrich (1983) and the apparently strong bond existing between mother/calf pairs (Whitehead, 1983).

While wintering on low-latitude breeding grounds, single, male humpback whales produce a complex, highly-structured series of sounds called "songs" which continually evolve (Winn and Winn, 1978; Payne et al., 1983; Guinee et al.,

1983). The song may last from 6-30 minutes and is repeated without noticeable breaks between sequences (Payne, 1970). Humpback whales from the North Atlantic have a different song from that of humpback whales in the North Pacific, suggesting North Atlantic and North Pacific dialects (Winn et al., 1981), while songs recorded from two distinct breeding grounds in the South Pacific were found to be similar (Payne and Guinee, 1983).

While humpback whale "songs" have also been recorded on the high latitude feeding grounds (Mattila et al., 1987; McSweeny et al., 1989), most of the vocalizations recorded appear to be much less structured (Winn et al., 1979). These "social" vocalizations, related to group size (Silber, 1986), are generally variable in frequency and duration. Although attempts have been made to categorize these sounds (Thompson et al., 1986; Chabot, 1988), their relationship to the behavior and social structure of the humpback whale has not yet been determined.

Humpback whales display a series of spectacular surface behaviors including breaching, flippering, spyhopping and lobtailing which are discussed in detail in Chapter 4. Herman Melville (1851) said, "He is the most gamesome and lighthearted of all whales, making more gay foam and white water generally than any of them." Although observed and studied by many, the exact function(s) of these behaviors remains unclear (Whitehead, 1985a,b).

successfully been have Individual humpback whales identified through photographic documentation of natural markings; especially pigment patterns on the ventral surface of the flukes (Katona and Whitehead, 1981). patterns, ranging in coloration from all-white to all-black, are not stable in some immature whales but appear to be generally stable in adults (Carlson et al., 1990). Acquired markings, such as parallel scars, believed to be caused primarily by the killer whale, Orcinus orca (Katona et. al, 1980; Whitehead and Glass, 1985), are useful for long-term identification of individual whales (Katona and Whitehead, confirm ability to 1981; Carlson, 1982). The identifications of individuals of this species is the key to detailed studies of population size and dynamics (Herman and Antinoja, 1977; Whitehead, 1982; Whitehead et al., 1983a,; Baker et al., 1985; Darling and Morowitz, 1986; Katona and Beard, 1990; Perry et al., 1990), seasonal return rate (Mayo, 1982; Glockner-Ferrari and Venus, 1983), temporal and spatial distribution (Whitehead et al., 1980; al., 1980; Baker and Herman, 1981; Mayo, 1982; Herman et and Moore, 1982; Darling and Jurasz, 1983), Whitehead organization (Whitehead, 1983) and calving rate social and Mayo, 1990; Glockner-Ferrari and Ferrari, (Clapham 1990).

## 1.1.1. Humpback whales of the western North Atlantic

Western North Atlantic humpback whales feed during spring, summer and fall in at least four, widely separated, high latitude areas; the Gulf of Maine (Mayo, 1982, 1983; Mayo et al, 1985), Newfoundland-Labrador (Whitehead et al., 1980, 1983b; Whitehead, 1983), Greenland (Whitehead et al., 1983a; Perkins et al., 1982, 1984), and Iceland (Brown, 1976; Martin et.al., 1984; Sigurjonsson and Gunnlaugsson, 1990). It has been found that the individual whales of these high-latitude areas constitute distinct subpopulations or "stocks", seldom mixing with whales of other areas during the feeding season (Katona et al., 1980; Katona and Beard, 1990).

Migration from the high-latitude feeding grounds to the West Indies generally occurs during late fall and early winter (Katona et al., 1980, Martin et al., 1984; Mattila et al., 1985). The largest known winter aggregation of western North Atlantic humpback whales is found on Silver Bank, off the coast of the Dominican Republic (Winn et al., 1975; Balcomb and Nichols, 1982; Whitehead, 1982; Whitehead and Moore, 1982; Mattila et al., 1985). Silver Bank, along with neighboring Navidad and Mouchoir Banks and Borinquen Bank off the coast of Puerto Rico (Mattila, 1983), appear to be areas where individual humpback whales from the highlatitude feeding grounds rix, possibly interbreed, and give birth to their young (Katona and Beard, 1990).

Generally during late winter and early spring, humpback whales of the western North Atlantic leave these low-latitude breeding and calving grounds, and return to their separate high latitude feeding areas.

## 1.2. Comparative studies

Comparative studies have been used extensively to answer Interspecific adaptation. about auestions intraspecific studies and studies of individuals attempt to examine how variation in behavior reflects differences in In this section I will review the three major ecology. discuss their comparative studies and οf groupings applicability to detailed studies of animal behavior.

#### 1.2.1. Interspecific comparisons

Interspecific comparisons may involve a few, or a pair of closely related species differing in an important aspect of their ecology. For example, Cullen (1957) examined the breeding behavior of the kittiwake, Rissa trydactyla, and compared it with that of the ground nesting gulls as a group. Her work indicates that the change to cliff nesting by the kittiwake affected many aspects of the life history of the species and led to morphological changes and behavioral alterations. While this type of study allows for the comparison of more detailed variables, it is not always possible to determine which ecological factor is responsible

for the evolution of a specific behavioral or morphological difference between two species (Clutton-Brock and Harvey, 1978).

Interspecific comparisons may also involve comparing a number of species categorized by ecological variables. Crook (1964), studied approximately 90 species of Weaver (Ploceinae) in an attempt to determine possible correlations between differences in social organization and ecology. Predation and food appeared to be the main selective pressures influencing the evolution of social Detailed studies of social organization organization. displayed by African antelope species (Jarman, 1974) demonstrated that they exhibit various types of social organization, each related to dispersion patterns of food Wiley's (1974) systematic study correlates social structure, life history patterns and ecology of 17 species of grouse (Tetraonidae) exhibiting a wide range of social structure and mating systems. Wiley's study exemplifies some general patterns in the evolution of mating systems among higher vertebrates. Clutton-Brock (1989) reviews and describes the distribution of mammalian mating systems. diversity in mammalian mating systems is interpreted through a "simple framework of ecological relationships governing effects of male assistance of female breeding success and the defensibility of females by males". Such qualitative comparisons are useful for revealing broad trends in evolution and general relationships between social organization and ecology. Generally, they have not helped us directly understand how differences between the behavior of individual animals of the same species relate to their ecology.

Quantitative comparisons testing qualitative hypotheses test associations statistics to behavioral and ecological traits (Clutton-Brock and Harvey, Harvey et al. (1978) examined sexual dimorphism in 1978). primate tooth size. Their results indicate that male tooth size is larger than expected in harem-forming species, sexual competition hypothesis for the supporting the Armitage (1981) evolution of larger teeth in males. examined the role of sociality as a life history tactic in of burrowing sciurids and concluded species reproductive effort is determined by body-size energetics. Patterns of association among body size, reproduction, physical and behavioral development and sociality in 17 closely related species of canids were studied by Bekoff et al. (1981). The analyses demonstrated a close relationship between life history tactics and behavioral patterns. quantitative relationships between specific traits restricts the analysis to variables measured along an ordinal scale on a reasonable sample of species (Clutton-Brock and Harvey, and therefore, many questions remain unanswered because of a paucity of data. Furthermore, it may be difficult to sort out the effects of different variables on the evolution of a trait. Questions about adaptive behavior may then be better examined by comparing differences in behavior between individuals of a single species.

## 1.2.2. Intraspecific or interindividual comparisons

Intraspecific or interindividual studies may involve comparing populations within a species in different parts of its range or individuals or groups within a population. This approach, complementary to the broad scale comparisons among species, looks at relationships between selection and behavior through studies of the behavior of individuals of Lack's (1966) studies on twenty-five the same species. species of birds, in various parts of their exhibiting a wide variety of feeding and breeding habitats, into how reproductive rates, provide insight dependent factors and dispersal relate to food supply and behavior in wild birds. Lack stresses the need long-term studies of wild populations based on knowledge of the natural ecology of the species involved and the importance of well-designed field experiments to help expediate this otherwise slow process.

Bertram (1975) analyzed and compared long-term records of adjacent prides of wild lions, <u>Panthera leo</u>, living in presumably similar environmental conditions. By comparing the two groups, it was possible to show that some aspects of

their reproduction are caused by factors within each pride and not factors common to both. Betram's study demonstrates of social factors, number there are а that unidentified, which are important in the reproduction of their social evolution of affect the lions and organization.

Rubenstein (1986) studied the ecology and sociality in a population of horses inhabiting Shackleford Banks, a barrier island off the east coast of North America. The horses exhibited a variety of adult association patterns that had important island different regions of the habitat structure and ecological differences in abundance and distribution of vegetation. His detailed observations of individuals examines a subset of social relationships; male-male, female-female, male-female and breeder-nonbreeder. These observations are the basis for his comparison and examination of equid (horses and zebras) social systems in general and the environmental and physical factors affecting their evolution.

# 1.2.3. Studies of individuals

Consistencies and variation in behavior should become apparent when detailed, long-term studies of known individuals in a population are conducted. Kummer (1968) documented the sociobiology of the hamadryas baboon, Papio hamadryas, over a 15 year period. This detailed study

highlights the social organization of the hamadryas; non-conventional by baboon standards. Long-term studies on the rhesus macaque, Macaca mulatta, population on Cay Santiago (Sade et. al., 1976; Drickamer, 1974), Japanese macaques, Macaca fuscata, at Arashiyama, (Koyama, et al., 1975), Takasakiyama (Masui et al., 1975) and Koshima (Kawai, 1965; Mori, 1975) in Japan and chimpanzees, Pan troglodytes, at Gombe Stream Park in Tanzania (Goodall, 1971; 1988) have provided much of the data on primate life history variables.

Goodall's study on the chimpanzees of Gombe now spans over 26 years and represents the longest continual field study of any mammalian species. This collaborative, cooperative, field research effort has shed new light on many aspects of chimpanzee behavior and contributed significantly to the understanding of the social structure, reproductive strategies and ranging and feeding behaviors of this species. The accumulation of series of detailed life histories of individuals with markedly different traits has added a dimension to the study of animal behavior and underlines the importance of longitudinal studies.

Moss' 14 year study of the African elephant, Loxodonta africana, in Amboseli National Park, Kenya has generated a series of papers on elephant social behavior, population dynamics and ecology. Moss (1983) and Moss and Poole (1983) describe the social organization of this population of approximately 680 individually identified elephants,

including 50 family units and 100 independent males. Moss (1981) examined the family units, composed of closely related females living in stable groups, and Poole and Moss (1981), Moss and Poole (1983) and Poole (1987) discuss the social behavior of adult males. The reproductive success of males and female choice are investigated in Poole (1989).

Long-term studies of killer whales, Orcinus orca (Bigg et al., 1990; Obesiuk et al., 1990;), and bottlenose dolphins, Tursiops truncatus (Wells and Scott, 1990), are clearly the on individually identified studies comprehensive cetaceans to date. Olesiuk et al. studied the life history and population dynamics of resident killer whales in the coastal waters of British Columbia and Washington state, while Bigg et al. examined their social organization and genealogy. The long-term stability of 30 pods (discrete long- term breeding units composed of the same individuals), individual whales, allows for direct 261 total of measurement of vital statistics. The absence of movement between pods permits an estimation of birth and mortality rates. Furthermore, these animals are non-migratory so that environmental controls acting on the dynamics of a pod occur Detailed information on the locally. reproductive parameters, annual natural mortality rates for adult males, females and juveniles, pod characteristics, size and movements and associations of individual orcas, has given us a clear perspective on the complex social structure and behavioral ecology of this species and insights into the sociality of toothed whales in general.

Wells and Scott's (1990) study of at least three adjacent populations of individually identified bottlenose dolphins along the central west coast of Florida has examined population structure and dynamics since 1970. The study focuses on one population of approximately 100 individuals, many of known gender and age. The long-term nature of this study and the high percentage of identifiable individuals has allowed for estimations of vital rates (e.g. fecundity rates, annual recruitment rate) and observations of social structure of this species.

Detailed, long-term studies of the southern right whale, Eubalaena australis (R. Payne et al., 1990), have generated invaluable data on reproductive parameters, migration, distribution, habitat use and group composition by area of a large, migratory species of baleen whale. Payne's study, initiated in 1970, continues to provide information on the life histories of over 900 individual whales, many of known sex.

Detailed studies such as these have the potential to, but have not yet, compared the behavior and strategies of individual cetaceans in different stages of their life history.

The work of Clutton-Brock et al. (1982) is a classic, long-term study of individuals within a population. The red

deer, <u>Cervus elaphus</u>, is ideal for this type of field research, because of its large body size, short life span and open, accessible habitat. This detailed study analyses and compares reproductive success and strategies of male and female red deer and examines the behavioral ecology of deer in the light of modern evolutionary theory.

It is clear that the most recent advances from research on behavioral and evolutionary ecology have come from a few detailed studies extending over several years of recognized individuals within a population. For many species of whales, particularly the baleen whales, studies of this nature are in their infancy. The work of Hoelzel et al. (1987) is an example of a study that begins to examine behavioral They have shown that differences between individuals. minke whales, Balaenoptera identifiable individually acutorostrata, have individual foraging specializations that They suggest that lasting and consistent. are specializations are associated with particular feeding areas and represent learned strategies.

The fluctuating environment, long migrations and widespread distribution of many species of baleen whales would
appear to robe them inaccessible for detailed studies.
However, robe active, long-term studies of local populations
(Clapham and Mayo, 1990; Dorsey et. al., 1990; GlocknerFerrari and Ferrari, 1990; R. Payne et al., 1990; Perry et.
al, 1990; Sears et al., 1990) have begun to reveal answers

to basic biological questions on reproductive parameters, migration, seasonal return rate, distribution and habitat use. Genetic studies may soon give us insight into the reproductive strategies, sociality and dispersion of individuals. The work presented here examines and compares behavioral differences between individual humpback whales during different stages of their life history.

#### CHAPTER 2. METHODS

#### 2.1. The study area

This study was primarily conducted in Massachusetts Bay The area of focus was Stellwagen Bank, a 2.1). glacial deposit of gravel and sand approximately 30 km. long Depths along the axis of the and as much as 10 km. wide. vary from the shallowest location, 20 m. deep along steep slope on the west side of the broad southern end as much as 40 m. in the shallowest areas of the to northwest end. The depths around the bank similarly vary, ranging from 50 m. along the gradual slope of the southeast side to 125 m. in the vicinity of the northeast edge. contrast to Stellwagen Bank, the southern part of the study area, eastern Cape Cod Bay, is a relatively level-bottomed basin, with depths ranging from 10 shallow is characterized The water approximately 50 m. salinities above 32% and sea surface temperatures range from -1 C in midwinter to 26 C in midsummer (G. Giese, unpublished data).

### 2.2. Whalewatching and research cruises

The observations presented in this study were made aboard the 30m. commercial whalewatching vessels DOLPHIN III, IV,




Figure 2.1. The study area.

V, and VI from 1979 to 1985 and the 12m. R/V HALOS from 1983 to 1985. The Dolphin Fleet ran four-hour cruises leaving Provincetown, Massachusetts one to three times a day during the period mid-April through October each year. The track of the vessels was dependent upon whale sightings and whale densities observed on previous trips. There was no predetermined pattern to the cruises. Dedicated cruises were initiated in the autumn of 1983 and were conducted throughout the year aboard the R/V HALOS. The number of cruises and the length of each field season are given in Table 2.1.

Approximately 80% of the cruises were made to the area on and around Stellwagen Bank. Most of the remaining cruises were made in Cape Cod Bay during the months of April and May, when concentrations of whales can be observed there.

#### 2.3. Data collection

When whales were sighted, information on the species, number of whales, time, LORAN-C location, behavior and the identity of individuals (when possible) was recorded. The vessel attempted to maintain a position relative to the animal so that the bow of the boat directly faced either side of the individuals' dorsal fin or tail. This position allowed photographs useful for individual identification to be taken.

Table 2.1. Number of cruises, length of field season, and number of individual humpback whales observed between 1979 and 1985.

YEAR	NO OF CRUISES	FIELD SEASON	NO OF INDIVIDUALS OBSERVED
1979	164	04/17-10/29	47
1980	313	04/12-10/24	79
1981	525	04/11-11/04	89
1982	581	04/11-11/18	141
1983	685	04/07-11/20	121
1984	715	01/06-12/31	191
1985	805	01/06-11/11	221

## 2.4. Photographic equipment and film

Photographs were taken using Pentax ME and MX cameras and Pentax lenses ranging from 28 - to 400mm, with skylight filters. Each camera body was equipped with a Pentax 2 - 5 frame/second power winder for sequential photographs, and a recording data back for coding individual observations. Kodak Tri-X and Ilford HP5 black and white film rated at ASA 400 was used.

## 2.5. Identification of individual whales

The humpback whale has a number of morphological features which make it particularly easy to study individuals. The most significant of these is the difference in pigmentation patterns on the ventral surface of the flukes (Katona and Kraus, 1979; Katona et al., 1980). Individual whales were identified by this pattern, as well as dorsal fin shape (Mayo 1982; Mayo et al., 1985) and prominent scarification (Carlson 1982). All whales were given names based on prominent natural markings; this nmemonic device was initiated to facilitate field data collection.

# 2.6. Analysis of photographs

Contact sheets were made for each exposed roll of film.

These were carefully analyzed and each frame was labeled with the name of a known individual humpback whale or numerically coded for unknown animals. A photographic

summary sheet was completed for each observation listing the date, file names of individuals in an association (whales were considered associated if they were within two body lengths of each other and generally synchronous in direction of movement and surfacing and diving behavior), data-back code (an alphanumeric code imprinted on negatives documenting film roll series, roll number, and observation) and field data sheet number (a numeric series issued to each field researcher to order data sheets by individual trips). Clear, well-focused photographs exhibiting field marks of each individual humpback whale were selected from each contact sheet to add to the established photographic catalog. All photographs used were printed using a 4 x 5 format on Kodak RC II Polycontrast paper.

#### 2.7. Database

During the course of this study 348 individual humpback whales were photographed. Using a modification of Glockner-Ferrari's (1983) underwater photographic technique based on True's (1904) description of the genital region of humpback whales, and observations of known whales with calves (section 2.10), the gender of 168 individuals of this population has been determined (Seipt et al., 1984). A calf is defined as a whale whose length is judged to be half or less than that of the accompanying whale presumed to be its mother, and thus, less than one year old. A calf is

generally observed to be in close association and behavioral synchrony with its mother. An adult is defined as an individual whose age is greater than or equal to four years. Whales previously observed as a calf and whose age is less than four years are classified as juveniles. Forty-four reproductively mature females (known females whose age was 4 years or older) were observed with a total of 72 calves; calving intervals varied from one to four years. Of the 49 calves born prior to the 1985 field season, 39 have been observed in at least one of the years following birth (Clapham and Mayo, 1987).

# 2.7.1. Data entry and selection of individual whales

Data on the time of sightings, locations, movements, general behavior and associations of these individuals over an eight year period were entered into a D-base III+ data management system.

One hundred and twenty-seven individual humpback whales of known gender, that had been observed for more than one year, were chosen for the study. These individuals are listed by year in Appendix I and summarized by gender, age and reproductive status in Table 2.2.

### 2.8. Behavioral measures

The following behavioral measures were examined in this study for each whale in each year. Measures of feeding,

breaching, spyhopping, flippering and lobtailing, as well as low respiration and near-boat events, were derived from observation periods of 10 minutes or more. The measures indicate whether or not an individual whale displayed a given behavior during an observation and are not representative of the total number or percent of time spent displaying that behavior.

- ARRIVAL TIME: The day of the first observed sighting within the study area (days from January 01).
- DEPARTURE TIME: The day of the last observed sighting within the study area (days from January 01).
- RESIDENCE TIME: The time period, in days, between arrival and departure.
- LARGE SCALE RANGE: Log of the greatest observed distance an individual was identified from the centroid of its Stellwagen range during the summer months.
- LOW LATITUDE OCCURRENCE: Observed presence or absence on the breeding grounds earlier that year.
- MEAN GROUP SIZE: Mean group size of observed associations excluding calves.
- LOW RESPIRATION EVENTS (Figure 2.2): The ratio of the number of observed periods of "rest" to the number of times observed.

- BREACHING (Figure 2.2): The ratio of the number of observations in which a whale was breaching to the number of times observed.
- NEAR-BOAT EVENTS (Figure 2.2): The ratio of the number of observations of an individual orienting towards vessels (within one body length) to the number of times observed.
- FEEDING (Figure 2.3): The ratio of the number of times observed surface feeding to the number of times observed.
- SOCIALITY: The ratio of the number of times observed associating with one or more other whales (not in feeding groups) to the number of time observed.
- FLIPPERING (Figure 2.3): The ratio of the number of observations of flippering to the number of times observed.
- LOBTAILING (Figure 2.4): The ratio of the number of of observations of lobtailing to the number of times observed.
- SPYHOPPING (Figure 2.4): The ratio of the number of observations of spyhopping to the number of time observed.
- RELATIVE DISTANCE: The average distance of the individual from the centroid of the positions of all
  animals sighted that year. Relative distance was

calculated by converting LORAN-C locations of all humpback whales sighted from 1979 - 1985 to kilometers using a modification of an algorithm developed by Charles Mayo (unpublished). The new coordinates were averaged by year for all humpback whales as well as by year for the 127 individuals in the study. The following equation was used to determine the distance of each individual by year, from the centroid of humpback whale distribution:

rel. dis. = 
$$\sqrt{(x - \overline{x})^2 + (y - \overline{y})^2}$$
 where

- x and y = the average of all converted
  Loran-C co-ordinates of an individual
  whale in a given year, and
- $\bar{x}$  and  $\bar{y}$  = the average of all converted Loran-C co-ordinates of all humpback whales in a given year.

A data set of variables (by individual, by year) was created using the SYSTAT 4.0 data editor and is shown in Appendix II.

## 2.9. Statistical analyses

The data for most variables in this study are not normally distributed, even after square root, arcsine and log (+1) transformations. The majority of the test statistics used therefore, are non-parametric. Parametric test statistics were used when the variables tested showed a normal distribution, or when it was necessary to factor out between year differences in behavior and no non-parametric routines were available. Statistical analyses were generally performed using SYSTAT routines (Wilkinson, 1987).

The results of many statistical tests are given (with individual significance levels) in this thesis. There will undoubtedly be Type I errors (significant effects not reflecting real differences), but these should be few. In this thesis, I will concentrate more on patterns rather than "significant" results of individual tests.







BREACHING: A jump; the head breaks the surface of the water with the body at a 45 to 90 degree angle; in the air, the whale spins on its long axis or does not spin and re-enters the water, usually on its side or back.






NEAR-BOAT: The whale, orient- LOW RESPIRATION: The whale ing to the vessel, displays a variety of activities including spyhopping, logging and flippering.

rests horizontally at the water surface without swimming, flippers extended from body, movement confined to drifting.

Figure 2.2. Descriptions and photographs of breaching behavior, near-boat behavior and low respiration events (resting) (Mayo et al., 1985).








LUNGE FEEDING: The whale rises forcefully with its mouth open through schools of fish or krill; this behavior usually associated with expulsion of bubbles. As water fills the mouth, the throat and belly of the whale expand, the ventral pleats unfold.








**FLIPPERING:** The whale rolls on its side or back, raises one or both flippers above water, and slaps the flipper(s) against the water surface.


Figure 2.3. Descriptions and photographs of lunge feeding behavior and flippering behavior (Mayo 2t al., 1985).







LOBTAILING: Head down, flukes are held above the surface and are forcefully slapped against the water.



**SPYHOPPING:** The whale slowly rises vertically in the water exposing the head, occasionally to the eyes and sinks back in the vertical position.

Figure 2.4. Descriptions and photographs of lobtailing behavior and spyhopping behavior (Mayo et al., 1985).

Table 2.2. Number of individual whales in study summarized by sex, reproductive status, and age. Occurrences=sighting of individual whale by year.

***************************************				
Number Number Number Number Number Number Number Number Number	of of of of of of	occurrences females occurrences females of k occurrences occurrences individuals occurrences	of  of now of of	individual whales
				individuals of age = 2 yrs27
				individuals of age = 3 yrs17
				individuals of age = 4 yrs12
				individuals of age $\geq$ 5 yrs16
Number	of	occurrences	of	known juveniles 69
				known adults293




Figure 2.5. Categories of fluke coloration.

# 2.9.1. Relationship between gender and fluke coloration and scarification

The dependence of fluke coloration and parallel scarification on gender was examined using Chi Squared Contingency Table tests.

# 2.9.2. General behavioral correlations

different behavioral variables Correlations between (average of units for each individual whale, each year) and Ammodytes variables and sandlance, spp., behavioral abundance and whale abundance were examined using Spearman Correlation Coefficient statistics. The data on sandlance abundance used for this study was collected on Stellwagen Bank and adjacent waters by National Marine Fisheries Center biologists during Northeast Fisheries Service, standardized spring and fall bottom trawl surveys. abundance of sandlance, expressed as the mean of the logtransformed number of sandlance per tow/year, was considered representative of Stellwagen Bank and is detailed in Payne et al. (1986). Whale abundance is expressed as number of whales/effort/year (Payne et al., 1990). Data on the occurrence of humbback whales was collected by naturalists working aboard commercial whalewatching vessels during the study period.

The behavioral correlations were further examined using principal components analysis to summarize relationships between variables in an attempt to provide summary variables

for use in later analysis. Varimax rotations did not substantially improve the interpretation of the factors and are therefore not presented.

## 2.9.3. Variation in behavior

The significance of differences in behavior with age, age-class (juvenile, adult), gender, reproductive status (lactating, pregnant) and year was examined using Kruskal-Wallis non-parametric one-way analysis of variance test. The Mann-Whitney U test was used for variables with 2 characters.

Two-way analysis of variance was used to differences between behaviors and age, age-class, gender and In no cases where significant reproductive status by year. interaction term the effects were found was significant, with the exception of flippering and lobtailing in pregnant and lactating females. These behaviors are not discussed for this class of whales because of biases in the field data collection (section 3.6).

Consistancies in the year to year behavior of individuals was examined using the Friedman two-way analysis of variance statistic. Variation in behavior by individual male and female, by year, was further examined using two-way analysis of variance. A subset of the data, including 16 males and 16 females observed over a three year period (1983-1985), was used for these analyses. The reduced data set

eliminated individuals not observed in each of the three years selected, lactating females and juveniles, and enabled the tests to be more easily performed, using the computer packages available.

Wilkinson (1989) multi-way box plots were used to provide simple graphic summary, using rank order statistics instead of means. They were originally presented by Tukey Multi-way plots show the (1977) as schematic plots. distribution of a single variable stratified across levels of a grouping variable and are useful for illustrating results of survey data on multiple groups. The notches implement simultaneous confidence intervals on the median of several groups. If the intervals do not overlap, one can be confident at approximately the 95% level that the group medians are different (McGill, Tukey and Larsen, 1978). median is marked by the center horizontal line; lower and upper hinges are the upper and lower edges of the box, respectively. The ends of the whiskers are the adjacent (usually outermost) values. An \* marks outside values and extreme outside values are marked with an O (Wilkinson, 1988).

#### CHAPTER 3. RESULTS

## 3.1. Fluke coloration and scarification

Initially, variables other than behavioral ones were also examined for this study. Due to a paucity of data many were excluded. Tests of fluke coloration and scarification however, indicate that there are some significant morphological differences between males and females and are therefore, briefly discussed.

Results of chi squared contingency test indicated a significant dependence of ventral surface fluke coloration pattern on gender (chi square=35.820 DF=6 P=<.001) with females showing generally darker flukes (Table 3.1).

The dependence of the presence of parallel scars on gender was significant (chi square=4.595 DF=1 P=<.05) with more males (24.5%) showing parallel scars than females (10.3%).

Table 3.1. Fluke coloration (as shown in Figure 2.5) listed by gender.

		COLORAT	ION		
GENDER	1 and 2	3	4	5	TOTAL
male	25	21	2	1	49
female	7	37	18	16	78

## 3.2. General behavioral correlations

Results of Principal Components analysis indicate that all the behavioral variables are fairly independent of each other (Table 3.2) with the exception of sociality and mean group size. The first five Eigenvalues are greater than one, accounting for only 59.31% of the total variance (15.81%, 12.72%, 11.71%, 10.29% and 8.78% respectively). The second principal component largely represents sociality and mean group size, and using it, individual whales may be arranged on a rough continuum, ranging from more social to less social individuals.

The matrix of Spearman Correlation coefficients (Table 3.3, 3.4, 3.5) generally mirrors the results of the Principal Components analysis and indicates the following important behavioral correlations by year:

- 1). Individuals that are more social arrive later and are a greater relative distance from the centroid of whale distribution, while less social individuals spyhop and flipper more, arrive earlier and stay longer.
- 2). Individuals that feed more, rest less.
- 3). During years when sandlance abundance was high, individuals flippered less, spyhopped less, arrived later, and were a greater distance from the centroid of whale distribution.

4). During years when whale abundance was high, individuals spyhopped more, flippered more, breached less, and stayed longer.

Table 3.2. Principal Component Analysis: Component loadings and Eigenvalues for those components with Eigenvalues greater than 1.0.

BEHAVIOR	COMPONENT LOADINGS					
	1	2	3	4	5	
Near-boat	-0.200	0.143	-0.517	0.307	0.410	
Lobtail	0.216	0.222	0.168	0.646	0.094	
Breach	0.083	0.330	0.473	0.517	-0.179	
Feeding	0.254	0.014	0.299	-0.317	-0.400	
Spyhop	-0.159	0.158	-0.426	0.212	0.143	
Social	0.350	0.771	-0.140	-0.245	0.060	
Flipper	-0.258	0.415	0.180	0.312	-0.412	
Resting	-0.381	0.170	0.069	0.080	0.258	
Arrive	0.513	-0.101	0.479	0.010	0.522	
Depart	-0.345	0.260	0.596	-0.290	0.481	
Reside	-0.797	0.268	0.078	-0.276	-0.030	
Mean group	0.407	0.702	-0.253	-0.286	-0.016	
Rel distance	0.576	-0.110	-0.145	-0.084	0.085	

EIGENVALUES						
1	2	3	4	5		
2.055	1.654	1.522	1.337	1.141		

Table 3.3. Matrix of Spearman correlation coefficients of mean values of behavioral variables for each year including spring/summer sandlance abundance (SL), average sandlance abundance (ASL), and whale abundance (MNABUND). Significant values (<.05) are highlighted.</p>

			<b></b>		Couchan
	Near-boat	Lobtail	Breach	Feeding	Spyhop
Near-boat	1.000				
Lobtail	0.432	1.000			
Breach	0.036	0.523	1.000	1 000	
Feeding	-0.429	-0.252	-0.321	1.000	1 000
Spyhop	-0.252	-0.455	-0.577	-0.090	1.000
Social	0.214	-0.090	0.429	-0.143	-0.721
Flipper	-0.018	-0.427	-0.613	-0.342	0.927
Resting	0.214	-0.108	0.179	-0.857	0.450
Arrive	0.500	0.018	0.464	-0.179	-0.703
Depart	0.321	-0.324	0.250	-0.286	-0.108
Reside	-0.429	-0.847	-0.464	-0.000	0.811
Mean group	0.393	-0.072	-0.357	0.250	0.414
Rel distance	0.464	-0.126	0.286	-0.000	-0.649
SL	0.468	0.200	0.378	0.252	-0.800
ASL	0.036	0.091	0.414	0.577	-0.564
MNABUND	-0.357	-0.667	-0.750	0.071	0.883
		_			
	Social	Flipper	Resting	Arrive	Depart
Social	1.000				
Flipper	-0.577	1.000			
Resting	-0.071	0.595	1.000		
Arrive	0.893	-0.559	0.036	1.000	
Depart	0.679	<b>~</b> 0.036	0.357	0.714	1.000
Reside	-0.250	0.739	0.429	-0.321	0.286
Mean group	~0.321	0.306	-0.036	-0.071	0.286
Rel distance	0.821	-0.523	-0.071	0.964	0.643
SL	0.667	-0.773	-0.396	0.847	0.396
ASL	0.342	-0.755	-0.505	0.523	0.216
MNABUND	-0.464	0.847	0.241	-0.607	-0.000
			-		
	Reside	Mean grp	Rel dist	SL	ASL
Reside	1.000				
Mean group	0.250	1.000			
Rel distance		0.000	1.000		
SL	-0.559	0.108	0.883	1.000	
ASL	-0.342	0.216	0.595	0.818	1.000
MNABUND	0.857	0.321	-0.536	-0.739	-0.595
	<del></del>	- · <del></del>			

Table 3.4. Matrix of Spearman correlation coefficients of mean values of behavioral variables, for each year, for juveniles, including spring/summer sandlance abundance (SL), average sandlance abundance (ASL), and whale abundance (MNABUND). Significant values (< .05) are highlighted.

	Near-boat	Lobtail	Breach	Feeding	Spyhop
Near-boat	1.000	DODUGII	Predon	10041119	~F1C
Lobtail	0.214	1.000			
Breach	0.179	0.357	1.000		
Feeding	-0.393	-0.107	-0.107	1.000	
Spyhop	0.143	-0.357	-0.750	-0.036	1.000
Social	0.464	0.357	0.036	0.107	-0.179
Flipper	0.321	-0.643	-0.179	-0.214	0.679
Resting	0.250	-0.071	0.286	-0.679	0.179
Arrive	0.179	0.357	0.464	0.393	-0.750
Depart	0.143	-0.571	0.321	0.321	-0.286
Reside	-0.071	-0.857	-0.393	-0.143	0.643
Rel distance	e 0.321	0.357	0.357	0.429	-0.464
SL	0.180	0.378	0.288	0.541	-0.541
ASL	-0.180	0.342	0.180	0.865	-0.324
Mean group	0.286	0.321	-0.286	0.179	0.286
MNABUND	-0.071	-0.857	-0.393	-0.143	0.643
			_		
	Social	Flipper	Resting	Arrive	Depart
Social	1.000				
Flipper	-0.357	1.000			
Resting	-0.643	0.571	1.000		
Arrive	0.571	-0.643	-0.571	1.000	
Depart	-0.071	0.286	-0.036	0.429	1.000
Reside	-0.357	0.857	0.321	-0.714	0.214
Rel distanc		-0.393	-0.286	0.821	0.464
$\mathtt{SL}$	0.414	-0.577	-0.541	0.919	0.396
ASL	0.234	-0.505	-0.613	0.887	0.216
Mean group	0.821	-0.143	-0.571	0.107	-0.429
MNABUND	-0.357	0.857	0.321	-0.714	0.214
	<b></b>	D.3 32-4		A CT	Moan arn
	Reside	Rel dist	SL	ASL	Mean grp
Reside	1.000	1 000			
Rel distanc		1.000	1 000		
SL	-0.739	0.955	1.000	1 000	
ASL	-0.595	0.739	0.818	1.000	1.000
Mean group	-0.107	-0.107	0.054	0.162	-0.107
MNABUND	1.000	-0.679			-0.10/

Table 3.5. Matrix of Spearman correlation coefficients of mean values of behavioral variables, by year, for adults, including spring/summer sandlance abundance (SL), average sandlance abundance (ASL), and whale abundance (MNABUND). Significant values (< .05) are highlighted.

	Near-boat	Lobtail	Breach	Feeding	Spyhop
Near-boat	1.000			-	<del></del> -
Lobtail	0.299	1.000			
Breach	0.090	0.679	1.000		
Feeding	-0.198	-0.393	-0.321	1.000	
Spyhop	-0.282	-0.450	-0.505	0.288	1.000
Social	0.144	-0.714	-0.286	0.606	0.288
Flipper	-0.252	-0.321	-0.643	-0.357	0.559
Resting	0.288	0.321	0.357	-0.964	-0.162
Arrive	0.703	-0.036	0.357	-0.107	-0.414
Depart	0.360	~0.179	0.429	-0.179	-0.018
Reside	-0.559	-0.786	-0.536	0.071	0.739
Rel distance	0.432	-0.321	0.214	0.071	-0.342
SL	0.627	0.090	0.378	0.252	-0.555
ASL	0.264	0.054	0.414	0.577	-0.209
Mean group	0.306	0.179	-0.000	0.536	0.487
MNABUND	-0.396	-0.643	-0.750	0.071	0.847
	_			_	
	Social	Flipper	Resting	Arrive	Depart
Social	1.000				
Flipper	-0.214	1.000			
Resting	-0.429	0.321	1.000		
Arrive	0.464	-0.571	0.250	1.000	
Depart	0.500	-0.357	0.393	0.821	1.000
Reside	0.321	0.643	-0.000	-0.321	0.107
SL	0.505	-0.811	-0.162	0.847	0.523
ASL	0.613	-0.811	-0.450	0.523	0.414
Mean group	0.321	-0.214	-0.393	-0.000	0.036
MNABUND	0.143	0.821	-0.036	-0.500	-0.179
	Reside	Rel dist	SL	ASL	Mean grp
Reside	1.000				
Rel distance	-0.107	1.000			
SL	-0.595	0.811	1.000		
ASL	-0.414	0.613	0.818	1.000	
Mean group	-0.179	-0.071	0.198	0.523	1.000
MNABUND	0.893	-0.393	- v <del></del>		-0.000
	_	_			


# 3.3. Variation in behavior with age-class

Mann-Whitney U test statistics indicated highly significant differences between age-classes in rates of near-boat behavior, lobtailing behavior, breaching behavior, spyhopping behavior, sociality, resting behavior, residence time, departure time and mean group size and significant relationships between age-class and rates of surface feeding behavior, flippering behavior and relative distance (Table Juveniles generally appeared to approach boats, 3.6). lobtail, breach, spyhop, flipper and rest more frequently than adults, while analyses indicated that adults surface Juveniles fed more frequently and were more social. appeared to leave the study area later and had a longer residence time than adults.

Box plots of age-class and rates of near-boat behavior, breaching behavior, lobtailing behavior and spyhopping behavior are shown in Figure 3.1; box plots of age-class and rates of resting behavior, surface feeding behavior, sociality and mean group size are shown in Figure 3.2; box plots of age-class and departure, residency, flippering behavior and relative distance are shown in Figure 3.3.

Table 3.6. Natural logs of mean scores for behavior by age-class with Mann-Whitney U Test statistics.

BEHAVIOR	JUVENILE	ADULT	MANN-WHITN STATISTIC	EY
Near boat	.146	.079	MW=10089 P=	<.001
Lobtail	.053	.042	MW=8963 P=	.002
Breach	.121	.096	MW=9056 P=	.003
Feeding	.127	.187	MW=6036 P=	.010
Spyhop	.032	.020	MW=9119 P=	<.001
Social	.467	.593	MW=4768 P=	<.001
Flipper	.071	.063	MW=8411 P=	.054
Resting	.083	.048	MW=9846 P=	<.001
Arrive	5.028	4.910	MW=9066 P=	.417
Depart	5.629	5.388	MW=11844 P=	004
Reside	4.640	4.023	MW=12199 P=	001
Mean group	1.058	1.147	MW=4792 P=	-<.001
Rel distance	1.303	1.594	MW=7943 P=	051



Pigure 3.1. Box plots of rates of near boat behavior,
 breaching behavior, lobtailing behavior and
 spyhopping behavior by age-class. N=357.




Figure 3.2. Box plots of rates of resting behavior, surface feeding behavior, sociality and mean group size by age-class. N=357.




Figure 3.3. Box plots of rates of departure, residency, flippering, and relative distance by age-class. N=357

The above analyses may be confounded by between year effects. In order to reduce these effects, two-way analysis of variance test statistics for behavior by age-class, by year were performed. The results of these analyses (Table significant differences highly 3.7) indicate juveniles and adults for near-boat events, feeding events, sociality, resting, time of residence, time of departure, centroid of distance from the relative and distribution and significant differences between juveniles and adults for breaching events and mean group size.

Although between year effects will be discussed in section 4.3, it is of interest to note here that no significant differences in within-year sighting data was found for the occurrence of juvenile males, juvenile females, adult males or adult females during the study period (Clapham et al., in review).

Table 3.7. Two-way analysis of variance test statistics for behavior by age-class by year.

BEHAVIOR	JUVEN	ILE/ADULT	YEAR		
	F-RATIO	PROBABILITY	F-RATIO		
Near-boat	18.093	<.001	3.483	.002	
Lobtail	.585	.445	1.037	.401	
Breach	6.145	.014	19.996	<.001	
Feeding	6.892	.009	2.332	.032	
Spyhop	2.327	.128	1.356	.232	
Social	1.382	<.001	14.653	.222	
Flipper	.867	.353	1.622	.141	
Rest	7.927	.005	1.037	.401	
Arrive	1.463	.227	1.550	.161	
Depart	5.111	.001	.909	.489	
Reside	10.204	.002	5.110	<.001	
Mean group	5.178	.025	2.302	.039	
Rel distance	6.862	.009	9.340	<.001	

# 3.4. Variation in behavior with age

Mean scores for behaviors by age as well as Kruskal-Wallis statistics are shown in Table 3.8. Analyses indicate that the relationships between age and sociality and age and mean group size were highly significant with sociality generally increasing with age. The relationship between resting and age was significant; rates of resting were greater for younger whales than mature ones.

Sociality, mean group size, rates of resting behavior and surface feeding behavior were plotted against age in Figure 3.4. Although not highly significant (Table 3.8), rates of surface feeding behavior were plotted against age to determine if general trends exist.

Two-way analysis of variance test statistics for behavior by age, by year (Table 3.9), indicate highly significant differences by age for sociality and mean group size and a significant difference by age for resting events.

Table 3.8. Natural logs of mean scores for behavior by age with Kruskal-Wallis test statistics.

			AGE			KRUSKAL- WALLIS
BEHAVIOR	1	2	3	4	5+	STATISTIC
Near-boat	.161	.136	.140	.142	.155	KW=.920 P=.90
Lobtail	.034	.078	.040	.034	.037	KW=6.09 P=.193
Breach	.125	.131	.102	.104	.093	KW=2.73 P=.604
Feeding	.084	.132	.181	.132	.153	KW=8.95 P=.062
Spyhop	.032	.026	.042	.051	.031	KW=3.75 P=,442
Social	.411	.473	.537	.538	.533	KW=14.3 P=.006
Flipper	.061	.080	.072	.094	.083	KW=.386 P=.818
Resting	.107	.075	.060	.056	.034	KW=9.42 P=.051
Arrive	5.092	4.986	5.004	5.042	4.991	KW=2.93 P=.570
Depart	5.636	5.627	5.620	5.623	5.445	KW=7.74 $P=.102$
Reside	4.507	4.714	4.716	4.678	4.127	KW=1.47 P=.322
Mean group	.988	1.067	1.143	1.141	1.148	
Rel dis	1.523	1.156	1.222	1.894	1.54	_




Figure 3.4. Sociality, mean group size, rates of resting behavior and surface feeding behavior plotted by age.

Table 3.9. Two-way analysis of variance test statistics for behavior by age, by year.

BEHAVIOR	A F-RATIO	GE PROBABILITY	YE F-RATIO	AR PROBABILITY
Near-boat	.289	.884	.920	.485
Lobtail	.583	.676	1.316	.259
Breach	.778	.542	1.612	.154
Feeding	1.932	.113	1.409	.221
Spyhop	.764	.552	2.845	.014
Social	4.069	.005	.555	.765
Flipper	.545	.703	1.105	.366
Resting	2.851	.029	1.031	.411
Arrive	.379	.823	4.581	<.001
Depart	1.815	.134	2.289	.043
Reside	1.614	.178	1.027	.414
Mean group	5.217	.001	1.819	.105

# 3.5. Variation in behavior with gender

Mann-Whitney U test statistics and mean scores for behavior by gender are shown in Table 3.10. Results indicate a significant relationship between gender and rates of surface feeding, sociality and arrival time; males generally fed more and arrived later than females; females generally were more social than males.

Box plots of rates of surface feeding behavior, sociality, arrival and relative distance, by gender, are shown in Figure 3.5.

Two-way Analysis of Variance Test statistics for behavior by gender, by year (Table 3.11), indicate highly significant differences between males and females for time of arrival and departure and a significant difference for feeding events. Parametric statistics indicate significant differences between gender and rates of feeding, arrival time and departure time. The relationship between gender and sociality suggested by the non-parametric analysis may be confounded by between year effects.

Table 3.10. Natural logs of mean scores for behavior by gender with Mann-Whitney U test statistics.

MALE	FEMALE	MANN-WHITNEY STATISTICS
.092	.103	MW=25090 P=.987
.045	.057	MW=25414 P=.785
.105	.113	MW=24869 P=.884
.197	.169	MW=27431 P=.033
.026	.020	MW=23041 P=.072
.509	.525	MW=28324 P=.018
.067	.055	MW=22930 P=.108
.052	.061	MW=26366 P=.320
5.101	4.895	MW=28122 P=.027
5.579	5.393	MW=29750 P=.217
4.184	4.019	MW=30926 P=.594
1.113	1.120	MW=26246 P=.394
1.530	1.633	MW=33240 P=.099
	.092 .045 .105 .197 .026 .509 .067 .052 5.101 5.579 4.184 1.113	.092 .103 .045 .057 .105 .113 .197 .169 .026 .020 .509 .525 .067 .055 .052 .061 5.101 4.895 5.579 5.393 4.184 4.019 1.113 1.120




Figure 3.5. Box plots of rates of surface feeding behavior, sociality and arrival by gender. N=463

Table 3.11. Two-way analysis of variance test statistics for behavior by gender, by year.

	GEN	DER	YEAR		
BEHAVIOR	F-RATIO	PROBABILITY	F-RATIO	PROBABILITY	
Near-boat	.341	.559	4.033	.001	
Lobtail	.307	.580	7.471	<.001	
Breach	.609	.435	17.079	<.001	
Feeding	4.640	.032	6.363	<.001	
Spyhop	.632	.422	1.452	.193	
Social	1.351	.246	1.889	.081	
Flipper	1.413	.235	4.350	<.001	
Resting	.875	.350	2.633	.016	
Arrive	7.735	.006	5.986	<.001	
Depart	7.183	.008	1.834	.091	
Reside	.339	.561	10.250	<.001	
Mean group	.268	.605	5.099	<.001	
Rel distanc	e .668	.414	19.890	<.001	

# 3.6. Variation in behavior with reproductive status

Mother-calf pairs breached and lobtailed more frequently than pregnant females, and arrived and departed from the study area later in the season while pregnant females were generally observed in larger groups and were more social (Table 3.12). Rates of breaching and lobtailing however, are confounded by the inclusion of calf behavior with that of the mother during field data collection. Since, in my data sets, it is impossible to separate the two, these relationships will not be considered in the discussion.

Box plots of rates of sociality ,mean group size, arrival and departure, by reproductive status, are shown in Figure 3.6.

Two-way analysis of variance test statistics for behavior by female reproductive status, by year (Table 3.13) indicate highly significant differences between pregnant and lactating females for breaching events, sociality, time of arrival and departure and a significant difference in mean group size.

Table 3.12. Natural logs of mean scores for behavior by reproductive status with Mann-Whitney U test statistics.

BEHAVIOR	LACTATING	PREGNANT	MANN-WHITNEY STATISTIC
Near-boat	.095	.071	MW=2309 P=.085
Lobtail	.052	.050	MW=2371 P=.034
Breach	.192	.118	MW=2688 P=<.001
Feeding	.149	.192	MW=1835 P=.486
Spyhop	.014	.012	MW=2201 P=.175
Social	.307	.530	MW=3021 P=<.001
Flipper	.048	.058	MW=2027 P=.797
Resting	.057	.059	MW=2035 P=.766
Arrive	4.828	4.609	MW=2876 P=.012
Depart	5.276	5.040	MW=3006 P=.002
Reside	3.819	3.620	MW=2618 P=.164
Mean group	.935	1.145	MW=2445 P=<.001
Rel distance	1.498	1.712	MW=1681 P=.148




Figure 3.6. Box plots of rates sociality, mean group size, arrival and departure by reproductive status. N=136.

Table 3.13. Two-way analysis of variance test statistics for behavior by reproductive status by year.

	PREGNAN	r/lactating	YE	AR
BEHAVIOR	F-RATIO		F-RATIO	
Near-boat	1.220	.272	1.323	.253
Lobtail	.028	.868	2.320	.037
Breach	8.672	.004	15.928	<.001
Feeding	1.111	.294	1.611	.150
Spyhop	.086	.770	1.710	.326
Social	11.274	<.001	4.154	<.001
Flipper	.080	.350	1.330	.249
Resting	.069	.793	.605	.726
Arrive	9.979	.002	5.277	<.001
Depart	18.168	<.001	3.712	<.001
Reside	1.274	.261	4.137	.001
Mean group	3.565	.061	6.685	<.001
Rel distance	e 1.391	.241	7.100	<.001

### 3.7. Variation by year

The relationships between all behavioral measures and year were significantly different (Table 3.14). The year 1979 was characterized by higher rates of near boat and breaching behavior, whales were generally more social, arrived later and were a greater distance from the centroid Rates of surface feeding behavior of whale distribution. were highest during 1980 and 1981; during 1981, whales were generally further from the centroid of distribution. During 1982 flippering, resting, generally long residence times and greater distances from the centroid of distribution were higher. During 1983, rates of flippering and resting were high; whales generally departed earlier and were closer to the centroid of distribution. Long residency periods were characteristic of 1984 and 1985. Rates of spyhopping and flippering were high during 1985; whales generally stayed longer, were in larger groups and were closer to the centroid of distribution than they were in any other year tested.

plots of rates of spyhopping behavior, breaching behavior, lobtailing behavior, flippering behavior, resting behavior and surface feeding behavior, by year, are shown in Figure 3.7; plots of rates of near-boat behavior, sociality, arrival, departure, residency and relative distance, by year, are shown in Figure 3.8.

Table 3.14. Natural logs of mean scores for behavior by year with Kruskal Wallis statistics (KW STAT).

				YEAR				
BEHAVIOR	1979	1980	1981	1982	1983	1984	1985	KW STAT
Near-boat	.157	.076	.121	.107	.078	.069	.112	KW=19.994 P=.003
Lobtail	.208	.071	.045	.038	.046	.026	.046	KW=23.255 P=.001
Breach	.356	.157	.086	.152	.109	.095	.077	
Feeding	.127	.271	.255	.165	.128	.184	.159	KW=29.084 P=<.001
Spyhop	.004	.016	.016	.027	.021	.017	.032	KW=38.468 P=<.001
Social	.579	.537	.564	.544	.523	.525	.494	KW=22.794 P=.001
Flipper	.028	.014	.038	.070	.070	.059	.076	KW=71.556 P=<.001
Resting	.070	.030	.038	.075	.071	.054	.055	KW=29.419 P=<.001
Arrive	5.380	4.977	5.099	5.021	4.837	5.013	4.795	KW=76.320 P=<.001
Depart	5.566	5.364	5.490	5.594	5.299	5.561	5.370	KW=65.721 P=<.001
Reside	2.711	3.356	3.739	4.410	4.098	4.358	4.357	KW=45.986 P=<.001
Mean grp	1.130	1.140	1.146	1.152	1.063	1.101	1.174	KW=34.812 P=<.001
Rel dist	1.946	1.725	2.125	1.907	1.180	1.809	1.031	




Figure 3.7. Rates of spyhopping behavior, breaching behavior, lobtailing behavior, flippering behavior, resting behavior and surface feeding behavior plotted by year.




Figure 3.8. Rates of near boat behavior, sociality, arrival, departure, residency and relative distance plotted by year.

# 3.8. Variation in behavior by individual

Friedman two-way analysis of variance test statistics for behavior by individual whale, by year (Table 3.15), indicate significant differences between individuals for near-boat, breaching and feeding events, time of residence, mean group size and sociality. Individual females tend to vary their behavior more than males except for boat approaches and arrival time.

Results for behavior by individual females (Table 3.16) indicate significant differences between individuals for feeding events, sociality, time of residence and mean group size. Results for males (Table 3.17) indicate significant differences between individuals for near-boat events and time of residence.

Two-way analysis of Variance Test statistics for behavior by individual females by year (Table 3.16), indicate highly significant differences between females for near-boat events, sociality, time of departure and mean group size and significant differences for breaching and feeding events. Results for males (Table 3.17) indicate a highly significant difference for near-boat events and significant differences for feeding events, time of arrival and time of residence.

Table 3.15. Friedman two-way analysis of variance test statistics (FTS) for behavior by individual by year.

BEHAVIOR		Males	FEMALES	ALL WHALES
Near-boat	FTS=	26.425	20.529	48.663
	P=	.023	.197	.023
Lobtail	FTS=	12.917	11.287	32.443
	P=	.533	.792	.396
Breach	FTS=	19.792	23.961	46.799
	P≕	.137	.090	.034
Feeding	FTS=	16.483	27.562	51.165
	P=	.285	.036	.013
Spyhop	FTS=	11.775	17.327	29.347
	P=	.624	.365	.551
Social	FTS=	20.817	28.268	52.400
	P==	.106	.029	.010
Flipper	FTS=	19.722	21.000	42.295
<u>-</u> -	P=	.137	.179	.085
Resting	FTS=	18.333	22.078	41.867
_	P=	.192	.141	.092
Arrive	FTS=	22.447	21.255	46.356
	P=	.070	.169	.038
Depart	FTS=	17.392	20.842	35.697
•	P=	.236	.210	.257
Reside	FTS=	23.792	27.824	48.244
	P=	.049	.033	.025
Mean group	FTS=	18.733	26.268	47.286
<b>-</b>	P=	.175	.050	.031
Rel distance	FTS=	17.333	24.680	41.212
	P=	.239	.076	.104

Table 3.16. Two-way analysis of variance test statistics for behavior by individual female, by year.

		FEMALE	YEAR		
BEHAVIOR	F-RATIO	PROBABILITY	F-RATIO	PROBABILITY	
Near-boat	3.321	.002	3.554	.041	
Lobtail	.893	.549	4.884	.015	
Breach	2.378	.021	1.440	.253	
Feeding	2.374	.021	1.293	.289	
Spyhop	.777	.691	1.995	.154	
Social	2.758	.009	6.153	.006	
Flipper	2.387	.020	2.411	.107	
Resting	.919	.554	3.243	.053	
Arrive	1.785	.086	2.432	.105	
Depart	2.805	.008	4.259	.024	
Reside	1.304	.260	.062	.940	
Mean group	3.780	.001	30.326	<.001	
Rel distance	1.896	.066	9.078	.001	

Table 3.17. Two-way analysis of variance test statistics for behavior by individual male, by year.

BEHAVIOR	MALE F-RATIO PROBABILITY		YE F-RATIO	AR PROBABILITY
Near-boat	3.447	.002	2.029	.149
Lobtail	.973	.504	.734	.489
Breach	1.827	.078	3.269	.052
Feeding	2.260	.028	1.725	.195
Spyhop	1.333	.244	.444	.645
Social	3.367	.331	.331	.721
Flipper	1.315	.254	1.078	.353
Resting	1.285	.271	.726	.492
Arrive	2.338	.023	7.952	.002
Depart	1.134	.371	20.460	<.001
Reside	2.173	.034	5.208	.011
Mean group	1.849	.074	3.107	.059
Rel distance	1.649	.119	1.873	.171

## 3.9. General highlights of results

- Parametric (including year effects) and non-parametric (without year effects) tests generally agree in significance of effects.
- 2). Female humpback whales have generally darker flukes than males, while males show more parallel scars than females.
- 3). There appears to be little correlation between behavioral variables, except that individual humpback whales may be arranged on a continuum based on sociality that is interlaced with related behavioral variables (especially relative distance, spyhopping, flippering and residence patterns).
- 4). During years when sandlance abundance was high, individuals flippered and spyhopped less, arrived later and were a greater distance from the centroid of whale distribution.
- 5). During years when whale abundance was high, individuals spyhopped more, flippered more, breached less and stayed longer.
- 6). Rates of resting are generally lower as individuals approach maturity, while rates of sociality generally increase.
- 7). All behavioral variables showed significant differences between the years of the study.

- 8). There is more variation in rates of behavior between juveniles and adults than is found between any other classes of whales tested (male/female, pregnant/lactating, age-class).
- 9). There is more consistent variability in sociality, group size and feeding rates between classes of whales (juvenile/adult, male/female, age-class and lactating/pregnant) than was found for any of the other variables tested.
- 10). There are significant, consistent (over years) individual differences in behavior, particularly among females.

## CHAPTER 4. DISCUSSION

## 4.1. Humpback whale behavior

Our understanding of whale behavior has greatly increased due to long-term field studies and the collection of quantitative, observational data. By examining the context of behaviors, various authors have discussed possible functions for specific activities (e.g. Tyack, 1982; Clark, 1983; Whitehead, 1985a,b; Waters and Whitehead, 1990). In this section, I will review the behavioral events examined in this study, compare them with similar activities in other species (when possible), and discuss their function in the context of the new data presented. Lastly, I will generally discuss between year differences in behavior.

## 4.1.1. Near-boat behavior

Near-boat approaches (Figure 2.2) have been observed in several species of cetaceans. Swartz (1986) reports that with light boat traffic in Laguna San Ignacio most gray whales, Eschrichtius robustus, are not disturbed and approximately 5% follow boats. Dalheim (1986) reports that the whales are primarily 'attracted' to small boats with idling engines. Norris et al. (1983) describe two encounters of gray whales approaching the 49m barkentine Regina Maris while she lay at anchor. The first encounter,

lasting approximately one hour, involved a juvenile unknown sex, circling around the vessel and rubbing lightly against her hull. One to three additional animals, also juveniles, approached Regina from time to time, always staying outside the primary animal. Payne et al. (1983) report that in southern right whales, Eubalaena australis, near-boat approaches only follow slow advances by boats; approaches to almost stationary vessels was reported by Leatherwood et al. (1982) in Southern Hemisphere minke whales and Donovan (1982 ms) for Bryde's whales in Peruvian waters. Watkins (1986) described the reactions to boats of four species of baleen whales in Cape Cod bay; right whales Eubaelaena glacialis, fin whales, Balaenoptera physalus, Balaenoptera acutorostrata, and humpback minke whales. whales. Over a period of years, gradual changes in reaction of the whales, varying with increased experience and levels of habituation, were recorded. Minke whales changed from 'frequent positive interest' to a relative lack of interest; fin whales changed from 'generally negative' to uninterested reactions, humpback whales dramatically changed 'strongly positive disinterest' to often 'relative reactions'.

Humpback whales that feed off of Cape Cod have often been observed approaching vessels, particularly commercial whale watching vessels and small motor vessels that are idling or drifting. Near-boat approaches to commercial whalewatching

vessels have lasted for periods of over one hour. The duration of the approach is not always determined by the whale(s); on many occasions the vessels attempt to back away from the whale(s) in order to return to port or allow another vessel to approach.

Examining the possible costs and benefits of near-boat approaches is beyond the scope of this paper. However, on some occasions, the approaches appeared to serve a specific function. During the summer of 1989, a mature female (SA-1, Salt) and her calf, approached commercial whalewatching vessels. Salt would swim away from the vessel and dive for periods of time exceeding 15 minutes while the calf remained within a few meters of the hull. The behavior of the calf ranged from resting to surface active behaviors (e.g. breaching, lobtailing) to rolling-over or spyhopping. would surface and orient to the calf, only to swim away after a few minutes, thus repeating the cycle. This general behavior was observed on more than one occasion and with other mother-calf pairs. It is possible that the idling vessel served as an acoustical indication of the calf's location. Near-boat approaches may involve active surface feeding by one or more individual whales as they feed upon thick shoal schools of bait fish that occasionally surface around and directly under drifting whalewatching vessels. Finally, in areas of moderate to heavy small-boat traffic, individual whales have been observed to orient close to the hull of drifting whalewatching vessels, away from fast moving boat(s), especially if the boats are actively pursuing the whale.

Generally however, during near-boat approaches, one or more whales will circle around, or under the boat and various behaviors (e.g. flippering, breaching, lobtailing, spyhopping), which may at other times serve different functions, may be observed (Evans, 1987; Watkins, 1986). During this study, juveniles and mother/calf approached boats significantly more than males, females, adults and pregnant females. It is of interest to note that both juvenile animals and mother-calf pairs are generally less social than other classes of whales. Watkins (1986) reported that 'young whales' would tend to investigate his vessel, even in the 'early period' of his study, when whales could be approached only occasionally. Similarities exist between Norris et al.'s (1983) description of two instances of near-boat approaches by juvenile gray whales and the majority of the approaches I have observed by juvenile humpback whales. Firstly, the object of the approach appears to be the hull of the vessel, especially below the They suggest waterline and towards the stern. the approaches could have had a sexual context, or the approaches of a juvenile to a mother whale. Secondly, in approaches involving two or more individual whales, one whale will oftentimes maintain an orientation closer to the boat than the others; occasionally, this involves light aggression towards the other whale(s). Many of the nearboat encounters with whales during this study have involved light contact with the vessel; both dorsal and ventral orientations to the hull have been observed. Although there is no evidence to interpret this behavior as sexual, it is a possibility. C. Haycock (personal communication) described a 'sickly', abandoned, humpback calf that continually approached commercial fishing and whalewatching vessels with its mouth open and tongue visible. The calf appeared to be attempting to suckle on the hull of the vessel, lending some support to Norris et al.'s speculation of juveniles approaching a 'mother whale'.

It is important to note that near-boat behavior is not characteristic of whale populations in all areas. For example, Swartz (1986) reports that during the southerly migration, in areas of heavy small boat traffic, gray whales rarely follow boats and more often avoid them. Baker et al. (1982) studied the effect of vessel traffic on the behavior of humpback whales in Southeastern Alaska during the summer of 1981 and reported no vessel approaches. F. Cawthorn (unpublished data) reported that Tongan humpback whales instantly fled upon an approach closer than 25 yds., attributing this behavior to the use of dynamite by Tongan natives while hunting the whales.

Why whales approach and orient to boats is not clear. It appears that near-boat approaches serve various functions to different classes of whales in different areas during various aspects of their life cycle (feeding, breeding, migration).

## 4.1.2. Breaching, flippering and lobtailing

Breaching, flippering and lobtailing, shown in Figures 2.2, 2.3 and 2.4, respectively, constitute the surface active behaviors examined in this study (with the exception of feeding which is discussed separately in section 4.1.3). (1874) first described these behaviors as Scammon characteristic of the humpback whale, however, they have been reported in other species of cetaceans including southern right whales (Clark, 1983; Payne, 1990), bowhead whales (Wursig et al., 1986), gray whales (Norris et al., 1983), sperm whales (Waters and Whitehead, 1990), minke whales (Eds and MacFarlane, 1987) and killer whales (Balcomb Although much speculation exists, the et al., 1980). function(s) of these behaviors remain unclear.

Whitehead's (1985a,b) reviews of humpback whale breaching, flippering and lobtailing discusses many of the theories of aerial behavior and analyses their nature, context and hydrodynamics. Interpretations of the function of these behaviors are numerous. For example, it has been suggested that breaching may aid in the removal of parasites

(Beale, 1893), signify a reaction to excitation (Madsen and Herman, 1980), serve a social or communicatory role (Norris et al., 1983; Clark, 1983; Baker and Herman, 1984; R. Payne, 1990), be related to feeding (Mitchell, 1974; Pryor, 1986) or amusement and play (Beale, 1893; Pryor, 1986). Whitehead's analysis indicates that these surface active behaviors may have multiple functions; there appear to be strong correlations, both intra and interspecifically, with sociality in general.

Results of this study indicate that breaching lobtailing behaviors are generally performed more by juveniles and mother-calf pairs than adults and that flippering is generally more common in juveniles. Ιf breaching, flippering and lobtailing are correlated with sociality (e.g. aggression, signalling, courtship), would be expected to occur in classes of animals that are generally more social, yet juveniles and mother/calf pairs are less social than the other classes of whales examined. Waters and Whitehead (1990) found that breaches and lobtails by sperm whales were often made singly and often circumstances which appeared to be nonsocial and Wursig et al. (1986) report that breaches, lobtails and flipper slaps by bowhead whales were usually carried out by lone whales. As with sperm whales (Waters and Whitehead, 1990) and Payne, 1990), breaches southern right whales (R. and lobtails, particularly by juvenile animals, may be play.

appears that the transition to adulthood is a time when individuals acquire skills that may be of intermediate and long-term benefit (Walters, 1987). Gentry (1974) observed adult-like behavior in 2 week-old sealions and concluded that play experience was a vehicle by which behavioral patterns present in the young are changed over time, manifesting themselves in the adult with extremely new functions.

Whitehead (1985a) reports on the seasonality of breaching behavior in humpback whales. He found that breaching is performed significantly more often in the winter than in the summer, and at times of important social interactions. Since mating and calving take place during the winter, social interactions then would be more important. The observations of juveniles performing these activities on the feeding grounds more commonly than adults may reflect the development of social patterns in the young as play and may indirectly support the general correlation with sociality.

### 4.1.3. Feeding

The feeding behavior of the humpback whale (Figure 2.3) has been described by many authors (eg. Jurasz and Jurasz, 1979; Hain et al., 1982; Weinrich et al.; 1985; Hays et al., 1985; Dolphin, 1987).

During this study, adults were observed surface feeding significantly more than juveniles, with males generally

feeding more than female whales. There was no significant difference in feeding rates between pregnant and lactating females.

Weinrich et al. (1985) examined habitat use patterns as a function of age and reproductive status in humpback whales. Juvenile whales denerally appeared to be outside of the feeding groups in areas that probably were 'suboptimal' for feeding, however the rates of feeding were not discussed. The lower rate of feeding by juveniles may best be explained by the different energetic needs of juveniles and adult whales. Adults primarily invest in reproductive success while juveniles invest in the building of muscle tissue and general growth. The latter requires a much lower caloric input (Weinrich et al., 1985; Brodie, 1968).

It is more difficult to interpret the differences in feeding between male and female humpback whales; published, quantitative data on intersexual differences in prey size and prey preference are generally lacking. However Mizue (1949) observed no noticeable difference in food type between male and female right whales, blue whales and humpback whales; Oshumi (1979) suggested that female minke whales fed more actively than males. Kawamura (1970) concluded that the stomach contents of male sei whales were greater in weight and volume than females, but that females fed more often.

A major problem in interpretation is that the feeding events examined in this thesis are all surface feeding events. It is difficult to say what proportion of total feeding time, or its efficiency, that this behavior represents. It is also possible, as suggested by Weinrich et al. (1985), that certain classes of whales may feed in sub-optimal areas or in different depth stratas of the water column. This may represent less of a problem when comparing juvenile and adult feeding rates as there is a high negative correlation between feeding and resting. The feeding differences may reflect the fact that juveniles spend more time resting than adults. Finally, intersexual differences in feeding may also reflect the migratory nature of males and females, particularly pregnant females. It is possible that pregnant females have a greater feeding range and 'search' more than other classes of whales. Wursig et al. (1986) found that pregnant bowhead whales generally fed alone and Bogoslovskaya et al. (1981; 1982) report that pregnant female gray whales are the most common individual feeders. In other words, feeding is not all it appears to be on the surface.

### 4.1.4. Spyhopping

Spyhopping (Figure 2.4) has been observed in gray whales, bowhead whales, humpback whales, right whales, sperm whales (Pryor, 1986) and killer whales (Balcomb et al., 1980).

Unlike most whale behavior, few theories concerning the nature or function of spyhopping exist. In a review on non acoustical communication behavior of the great whales, Pryor (1986) reported that spyhopping is generally associated with visual inspection. L. H. Weilgart and H. Whitehead (personal communication) found а correlation between spyhopping and resting in sperm whales.

This study indicates that juveniles generally spyhop more than adults and that there is a slight tendency for males to spyhop more than females. Spyhopping is often observed, but is not correlated with near-boat approaches. This is most likely due to the fact the approaches are more characteristic of juvenile whales.

Although visual inspection of the air environment seems to be the most common interpretation of spyhopping, the whales' eyes are not always visible (C. Carlson, personal observation). Spyhopping therefore, may serve several functions. Whales resting in a vertical position, being slightly buoyant, may end up with part of their rostrum (snouts) above the surface of the water, or spyhopping may be the result of the maneuvering of a whale in an active social group or to a vessel. Quantitative observations for comparisons of spyhopping and group size in humpback whales are not yet available. Such data are necessary to further examine the nature of this activity, especially in a social context.

### 4.1.5. Low respiration or resting

Low respiration events or resting (Figure cetaceans has been described by many authors. McCormick (1969) described two types of resting behavior in bottlenose dolphins, Tursiops truncatus, and the Pacific white-sided dolphin, Lagenorhyncus obliquidens, the light and deep sleep phases. The deep sleep phase, by description, is similar to that observed in large baleen whales. Ljungblad et al. (1986) report on resting rates of bowhead whales in the northern Berring Sea, southern and coastal Chukchi Sea and the Beaufort Sea, Clark (1983) describes resting behavior of the southern right whale in Peninsula Valdes, Argentina, and Condy et al. (1978) describe the resting behavior of groups of killer whales, Orcinus orca at Marion Island (Prince Edward Island group). Norris et al.'s (1983) description of the resting behavior of gray whale mother-calf pairs in the breeding lagoons of Baja, California is similar to the reports of mother-calf humpback whales in Hawaiin waters by Glockner-Ferrari and Venus (1983). The mother/calf pairs were observed to 'float', remaining 'quiet' for long periods of time. These accounts of resting behavior are, for the most part, descriptive and do not allow for interspecific or intraspecific comparisons.

This study indicates that juveniles rest significantly more frequently than adult whales, lactating females and pregnant females. Interpretation of these results is

difficult as there is a paucity of published, quantitative data on resting behavior.

Interspecific comparisons have been conducted on the sleep patterns of 69 species of mammals (Elgar et al., 1988). Their study shows consistent patterns of associations between sleep variables and aspects of a species morphology, metabolic rate and development. The time spent in 'quiet sleep' was negatively correlated with body size and basal metabolic rate. They suggest that the duration of quiet sleep may reflect foraging requirements of the species.

Juveniles and adult humpback whales differ, among other ways, in their energetic needs. As mentioned in section 4.1.3, adults primarily need energy for reproduction and the building of fat while younger whales need energy for the building of muscle tissue and growth. According to Brodie (1968), the development of muscle tissue requires a much lower caloric input. This may help to explain the negative correlation between feeding and resting and may lend support to the speculation by Elgar et al. (1988) that sleep may reflect foraging requirements.

The function of rest in juvenile whales is not clear and probably serves many functions. While one of the functions may be to facilitate growth and development, it is possible that the comparatively low caloric input needed by juveniles

and aspects of their sociality may have helped to maintain the resting behavior observed.

## 4.1.6. Sociality/ Mean group size

Alexander (1974) stated that ecological factors forming the evolution of social groups may fall in two main classes: predator pressure and resource distribution. Wrangham and Rubenstein (1987) added that it is important to recognize intraspecific competition as a third class.

Results of this study on sociality and group size indicate that there are distinct differences in the rates of sociality between different classes of humpback whales. Adults are generally more social than juveniles, females more than males and pregnant females more than lactating ones. With the exception of a few observations of long-term associations on feeding grounds (Baker et al., Weinrich et al., 1985) and the strong bond between mothercalf pairs (Whitehead, 1983; Clapham and Mayo, 1987), the nature of the associations appear to be casual. This type of association has been reported in other species. example, Jarman and Southwell (1986) examined the sociality of eastern Grey Kangaroos, Macropus giganteus, and reported that group size is not limited by tight and closed associations of individuals (other than mothers and their of associations varied young). Frequencies between individuals and even the most frequently associating individuals were not always found together.

What are the possible factors influencing sociality in humpback whales? Although predation risks have been reported as a possible factor influencing the formation of groups in some species of whales (e.g. Best, 1979; Arnbom and Whitehead, 1989), this does not appear to be a causal factor in the population of humpback whales in this study. There have been no reports of predator attacks (such as Orcinus orca) on humpback whales in the southern Gulf of Maine. Furthermore, although tooth scars have been observed on individual whales in this population, only two incidents of known whales observed with 'new' tooth marks have been In both cases, the individuals were lactating females returning with calves and had clearly been attacked by a predator (C. Carlson, personal observation). The scars on the females were healed, indicating that the attack may have occurred on the breeding grounds or during the migration north.

More probable is the influence of resource distribution and prey patch size. This has been demonstrated in a number of species (e.g. Kummer, 1971; Jarman, 1974; Vehara, 1986; Wrangham, 1986) including whales. Wursig et al. (1986) report that bowhead whales occur in aggregations and are not randomly distributed on the feeding grounds. The size and distribution of these aggregations changes dramatically from

year to year and appears to be related to the general productivity of the area. Whitehead (1983) reported that the group size of humpback whales off Newfoundland was correlated with the size of the prey schools they were feeding on. This 'casual' sociality during feeding has also been observed in chimpanzees (Reynolds, 1965) where groups of variable sizes break-up and re-form, apparently in direct response to the availability of food.

Examining the factors that may affect sociality in humpback whales may be related to, but is not the same as examining why there are differences in sociality between various classes of whales. In this study, sociality is generally correlated with age. As an individual humpback whale approaches sexual maturity, its rate of social interactions and feeding generally increases while rates of resting decrease.

The sociality of pregnant and lactating humpback whales on low-latitude breeding grounds is markedly different from that observed on high-latitude feeding grounds. Mobley and Herman (1985) report that groups of whales with calves were generally characterized by a triad of mother, calf and 'escort', generally a male (Glockner-Ferrari and Ferrari, 1985; Mobley and Herman, 1985). When no calf was observed, singletons and pairs were most frequently Furthermore, groups with a calf would tend to take on new members far more readily than to lose them. Herman and Antinoja (1977) and Glockner-Ferrari and Ferrari (1985) also report a high incidence of accompaniment of mother-calf pairs on the Hawaiin breeding grounds. Tyack and Whitehead (1983) proposed that the 'escorts' in breeding areas may be mature males seeking access to estrus females. This has generally been supported by recent data (e.g. Glockner-Ferrari, 1985; Mobley and Herman, 1985). By contrast, there is a low incidence of accompaniment of mother-calf humpback whales in feeding areas (Nemoto, 1964; Weinrich et al., 1985; Clapham and Mayo, 1987). This may be partly explained by the fact that opportunities for a mature male to mate with a female are presumably generally restricted to winter breeding areas. It is also possible that the low incidence of associations by mother-calf pairs on the feeding grounds may help to reduce feeding competition. Segregation of mother/calf pairs on summer feeding grounds has reported by Wursig et al. (1986) in bowhead whales, Ljungblad et al. (1985) in gray whales and Kasamatsu and Ohsumi (1981) in minke whales. It is more difficult to explain why pregnant females are significantly more social than mother-calf pairs. One advantage of an associate might be to enhance acoustical vigilance for feeding whales. Using this information may direct attention to the area where a group of whales are successfully foraging and may therefore enhance feeding efficiency. It seems unlikely that forming an association would greatly increase feeding competition, as humpback whales are often observed in pairs. Whitehead (1983) and Clapham and Mayo (1987) report that the majority of observations, excluding feeding groups, of humpback whales on the feeding grounds were of single animals or pairs.

Results of this study further show that females are generally more social than males. It is possible, that in females, an associate may help to increase feeding efficiency while the feeding strategy of males may be to actively search for productive areas within their feeding range. As female reproductive success is generally related to absolute food intake, and male reproductive success to relative (to the other males) food intake, it may pay males to adopt the risky strategy of searching in more unusual places for large prey concentrations which would not be discovered by other males. It is also possible that males may be more efficient at feeding than females as reported by Kawamura (1970) in sei whales.

### 4.1.7. Arrival, departure and residency

Age and sex-related segregation during the migration of baleen whales from summer feeding grounds to winter breeding grounds has been described by many authors. Rice and Wolman (1971) and Swartz (1986) report on temporal segregation of gray whales on migrations to and from the lagoons at Baja, California. Late pregnant females lead the southward

migration followed by resting females, immature females. adult males and lastly immature males. The northward migration is led by newly pregnant females, followed by adult males, anoestrus females, immature males and finally, mother-calf pairs. Clark (1983) reports that the succession of arrival for southern right whales in Golfo San Jose, Peninsula Valdes, Argentina, is similar to that described for gray whales. Immature and female sei whales are observed early on the breeding grounds (Gambell, 1968) with a predomination of mature whales and males later. Pregnant females are the first to leave for the polar feeding grounds. In blue whales and fin whales (Mackintosh, 1942; Laws, 1961), male and pregnant females are the first to arrive in the Antarctic, followed by resting females and finally, mother-calf pairs. The order of the return migration is the same with post-lactation females joining the resting class. Best (1982) noted that minke whales show a segregation by sex during their winter migration with mature males outnumbering the females by more than 2 to 1, and a segregation by size in females with mature females arriving later than immature ones. Chittleborough (1958) and Dawbin (1966) describe known migratory routes of Southern Hemisphere humpback whales. They report that lactating females with their weaning calves led the migration to the breeding grounds followed by immature whales, mature males and resting females and finally, females in late pregnancy. The return migration is led by females in early pregnancy, followed by immature whales, resting females and mature males, and lastly, mother/calf pairs.

The results of this study generally indicate that females arrive earlier than males, adults arrive earlier than juveniles and pregnant females arrive earlier than mothercalf pairs. Results further indicate that pregnant females are the first to arrive on the feeding grounds and suggest that adults generally leave earlier than juveniles, females generally leave earlier than males, and pregnant females generally leave earlier than mother-calf pairs. My analysis of residency time indicates that juveniles generally remain longer than adults, males remain slightly longer than females, and mother-calf pairs remain longer than pregnant females.

It is difficult to discuss the succession of arrival, departure and residency time in the context of these results considering the nature of the observations. Recorded observations of arrival and departure indicate the dates that an individual whale was first and last photographed. They do not necessarily indicate the actual date that the individuals arrived from or left for the breeding grounds. Coverage of the study area before April and after October in most of the years of this study was minimal and it is also

possible that other humpback whales were present in areas that we were not able to survey.

It may be of interest however, to examine the general trends of a specific class, pregnant and lactating females, in the context of the data presented and existing knowledge of the feeding range and distribution of this population of humpback whales. The early sightings of pregnant females in the study area is in agreement with Dawbin's (1966) account of the early arrival of females on the feeding grounds. Yet, contrary to Dawbin's finding, pregnant generally leave the study area earlier than mother/calf pairs. Considering the energetic needs of pregnant females this appears to be counter-intuitive, less the nature of the study area and movements of individuals are examined. Clapham and Mayo (1987) report that mature females were observed significantly more frequently (on a greater number of days) in years when they had a calf than in years when they did not. Furthermore, pregnant females, observed off Brier Island, Nova Scotia, are often observed on Stellwagen Bank in years when they have calves (C. Haycock, unpublished It is possible that the apparent early departure of pregnant females from the study area actually reflects their greater feeding range and search activities than those shown mother-calf pairs. by Learning the broad range of traditional feeding grounds may make them more adaptive to prey changes. For example, Bi-2 (Binoc) was observed on a number of occasions feeding on northern Stellwagen Bank during the summers of 1980, 1981 and 1982. Her distribution pattern and residency time changed dramatically during 1983 when she was observed feeding on both northern and southern Stellwagen Bank during spring summer and fall. Binoc returned in 1984 to southern Stellwagen with her first observed calf. Finally, Stellwagen Bank may be an optimum area for mother-calf pairs as it provides them with shallow waters, an adequate food supply, and general freedom from predators (e.g. Orcinus orca) while the adjacent near-shore waters may provide some protection from rough weather (Clapham and Mayo, 1987).

### 4.1.8. Relative distance

Relative distance (in the context of this study), defined as the average distance of the individual from the centroid of the positions of all animals sighted that year, is described in detail in section 2.9.

Some of the literature on the distribution of baleen whales generally examines segregation by age, sex or reproductive status. Norris et al. (1983) and Swartz (1986) discuss the marked segregation of mother/calf gray whales in the breeding lagoons and Swartz (1986) details segregation on the feeding grounds. Mother-calf gray whales in Laguna San Ignacio differ in their distribution, swimming patterns, group size and residency from other classes of animals.

Although they routinely travel the length of the lagoon, they tend to concentrate in areas away from those frequented by other whales. Norris et al. (1983) states that the activity of the sexually active groups may be disruptive to mother-calf pairs and may even cause separation. Segregation also exists in the Arctic feeding grounds. Ljungblad et al. (1985)reported mother calf/pairs distributed in specific near-shore areas of the northern Bering and eastern Chukchi Seas; Yablokov and Bogoslovskaya (1984) describe age differentiation of a stock, with young animals congregated near the Koyak coastline while groups of adults were found in more northerly waters; Bogoslovskaya et al. (1982) report that Soviet whaling records indicate that small animals predominated the catches from specific coastal waters, mother-calf pairs were distributed in shallow coastal waters and larger animals were found offshore. The segregation of gray whales appears to be a behavioral characteristic that prevails throughout the species range (Swartz, 1986). Wursig et al. (1986) report that bowhead whales, in the Canadian Beaufort Sea, occur in aggregations with a tendency for mother-calf pairs to be segregated from other whales. Clark (1983) found that mother/calf southern right whales reside in shallow water and are segregated from other groups which generally remain offshore; Kraus and Prescott (1985) report a spatial segregation in North Atlantic right whale mother-calf pairs from the more active

groups offshore. Kasamatsu and Oshumi (1981) conclude that Southern Hemisphere minke whales show temporal and spatial intersexual segregation on high latitude feeding grounds. Males are more abundant in lower latitudes while females are observed more frequently in higher latitudes, near the ice Also, mother/calf pairs are only observed edae. temperate waters at lower latitudes during this season. Tarasevich (1967) reports that North Pacific fin whales form a variety of groupings on the feeding grounds, with males generally forming larger groups than females. Larger, older, mature fin whales occur alone or in groups of their own sex, while smaller and younger, mature animals generally occur in mixed groups. Jurasz and Jurasz (1979) and Baker et al. (1985) report that segregation by size, age, sex or reproductive condition in humpback whales on Alaskan feeding not observed. Goodale (1981)examined latitudinal and longitudinal distribution between humpback whale mother-calf pairs and animals without calves between Cape Hatteras, North Carolina and Nova Scotia. Significant differences between the two classes was found in the water depth, with mother/calf pairs found significantly more in shallow water. Weinrich et al. (1985) conclude that the humpback whale population of Stellwagen Bank and Jeffreys Ledge (Massachusetts) is comprised of three components: surface feeding groups, juveniles and mother-calf pairs.

They report that the groups are often present in different temporal and spacial patterns.

Results of this study indicate that adult whales are significantly further from the centroid of whale distribution than juvenile animals and that (although not highly significant) females are on average further than males.

The segregation of juveniles from adult animals generally support the findings of Weinrich et al. (1985), unless the centroid of whale distribution is coincident with areas of heavy surface feeding activity. These data indicate that this is probably not the case as adult whales were observed surface feeding significantly more than juvenile animals. It may better be explained by the general use of the study area during the duration of this study. Although Stellwagen Bank is an important area for humpback whales (Mayo, 1982), distribution and habitat use vary from year to year. many occasions, juvenile whales were observed in the area for a number of consecutive days when no known adult whales were observed (C. Carlson, personal observation) while large, surface feeding aggregations were reported to the north and/or southeast of the study area. It is possible that juvenile animals generally roam less and establish more defined seasonal ranges than do mature animals energetic needs may require searching for productive areas in a patchy environment. Some evidence for seasonal 'site tenacity' by juvenile animals is reported by Mayo (1982).

The fact that mother-calf pairs do not generally appear to segregate from other classes of whales is in agreement with the observations of Jurasz and Jurasz (1979) and Baker et al. (1985), but does not necessarily disagree with the findings of Goodale (1981). This may reflect the fact that Stellwagen Bank, a generally heavy use area for whales, also provides mother-calf pairs with a number of advantages, including shallow water. This is detailed in section 4.1.7.

There appears to be a slight tendency for females to be further from the centroid of whale distribution than males. This may reflect, in part, the possibility that pregnant females roam more (section 4.1.7) or that the behavior of individual females generally varies more than that of males (section 4.2). Wursig et al. (1986) observed that pregnant bowhead whales generally fed alone, which would, in part, explain this finding. Unfortunately, for my study, quantitative data on feeding group size and composition are lacking. Furthermore, the centroid of whale distribution as defined in this study, is the centroid of distribution as found by the whalewatching vessels.

# 4.2. <u>Individual differences in behavior</u>

Differences in the behavior of individuals have been reported in a variety of species (e.g. Lopez, 1978; Clutton-

Brock et al., 1982; Armitage, 1986; Goodall, 1988). Studies of this nature, particularly in baleen whales, are generally lacking. However, a few studies have begun to examine behavioral differences between individual whales. D'Vincent et al. (1989) studied cooperative lunge feeding among groups of humpback whales off southeast Alaska. They report that the groups were characterized by tightly clumped individuals that appeared to follow the cues of 1 or 2 lead individuals, rather than relying on combined sensory integration of all members during lunge feeding events. Hoeltzel et al. (1989) collected data on 23 individually identifiable minke whales around the San Juan Islands. Most individuals specialized on one of two feeding strategies that were consistent over a period of 5 years. Each strategy was associated with a particular feeding area. They suggest that the individual specializations represent learned strategies and are adapted to variations in the distribution of the same prey species. Hays et al. (1985) report on a unique feeding strategy of an individual humpback whale in the presence of other 'normally feeding! whales, suggesting that individual whales utilize several techniques in an effort to concentrate prey. The whale, a female named Cats Paw, has been observed off Cape Cod, Massachusetts since 1982 and can be readily identified by her distinct, consistent style of feeding. Schilling et al. (1991), reported on the spread of a novel feeding behavior, lobtailing before feeding (LTA), from 1980 to 1989. 12.5% of the whales first photographed before 1982 were observed LTA feeding as opposed to 56.2% first photographed after 1982.

Results of my study indicate that there are significant differences between individuals for rates of near-boat, breaching and feeding events, time of residence, mean group size and sociality and that females tend to vary their behavior more than males.

Although it is beyond the scope of this study to analyze the behavior of individual humpback whales in terms of costs, benefits or individual life strategies, data on individual differences in behavior may have more than academic applications.

Individual behavioral differences may have profound importance for the management of marine mammals threatened by pollution and/or commercial fisheries (Harwood, 1990). Harwood states that management policies will have to recognize the variability between individuals and not focus on "a mythical average seal or whale". Variable levels of bioaccumulating environmental contaminents in individuals of the same sex and age group from a particular area may be the result of individual foraging strategies. Harwood further states that the development of modern techniques such as biopsy sampling and telemetry may lead to the identification of "pollutant hot-spots".

Finally, culling marine mammals that may be accused of competing for fish resources with commercial fisherman may not solve the perceived problem, particularly if individuals are developing different feeding strategies and the cull does not target the "offenders".

## 4.3. Between-year differences in behavior

behavioral variables examined showed significant differences between all years of this study. This is hardly surprising considering the variable and unpredictable environment of humpback whales. To examine these differences fully, it would be necessary to construct a matrix which would include a vast number of physical, biological and behavioral variables. Clearly, it is beyond the scope of this thesis to attempt such a task. It is possible however, to begin to address these differences by examining possible relationships between all behavioral variables and sandlance abundance and whale abundance.

## 4.3.1. Sandlance abundance

Although the humpback whale has been described as a generalist in feeding habits (Mitchell, 1974), recent observations of feeding humpbacks in the Gulf of Maine indicate that sandlance have become an increasingly important prey species (Hain et al., 1982; Mayo, 1982) and the only prey species significantly correlated with humpback

whale distribution in the Gulf of Maine between 1978 and 1982 (Payne et al., 1986; 1990). Strong correlations between the distribution of humpback whales and density and distribution of particular prey has also been reported in other areas (eg. Lien and Merdsoy, 1979; Whitehead and Carscadden, 1985).

Results of this study indicate that during years of high sandlance abundance, individual whales flippered and spyhopped less, arrived later and were a greater distance from the centroid of whale distribution.

The distance of whales from the centroid of whale distribution may well reflect the distibution of prey, as Payne et al. (1986; 1990) have concluded from their analysis. Late arrival may suggest that individuals from the Gulf of Maine stock spend time feeding in offshore or more southerly waters before arriving in the Stellwagen This would support Kenney et al.'s (1981) suggestion area. that, for the Gulf of Maine stock, the Great South Channel is the major exit/entry between the Gulf of Maine feeding area and the deeper, offshore migration route. Correlations with prey apundance and flippering and spyhopping are more difficult to speculate on as the function(s) of these behaviors remain unclear. It is possible however, that flippering, if used as a "signal", is more functional when there is less distance between individual whales. particularly adults (Table 3.5).

Additionally, juveniles surface fed significantly more during years when prey abundance was high (Table 3.4). This may indirectly support the findings by Weinrich et al. (1985) that juveniles generally appear to be in "suboptimal" areas or feed in different areas of the water column.

## 4.3.2. Whale abundance

Whale abundance was negatively correlated with breaching and positively correlated with spyhopping, flippering and long residency time. There is a significant negative correlation with breaching and whale abundance and a significant positive correlation with spyhopping and whale abundance in adults, while there is a significant negative correlation between lobtailing and whale abundance in juveniles. Interpretation of these data is difficult; as mentioned earlier, the function of these surface behaviors remains unclear.

Furthermore, interpretation of these data in general are complicated by the complexity of the relationships of the numerous variables that may affect between-year differences in behavior.

#### CONCLUSIONS

Information on the differences in behavior of classes of whales, as presented in this thesis, should be of importance to future behavioral studies examining the function(s) of behaviors which remain unclear. Furthermore, this work may serve as a model of how to compare various classes of individuals in other whale studies.

Lastly, individual behavioral differences may have important management implications. Management policies should begin to recognize the variability between individuals and not focus on an "average whale". For it is clear that sound management policies are necessary for the survival of species, particularly one as endangered as the humpback whale.

# APPENDIX I

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
ABRAXUS	AB1	1980	F	Ū	Ŭ	U
ABRAXUS	AB1	1981	F	U	U	U
ABRAXUS	AB1	1982	F	Ŭ	U	U
ABRAXUS	AB1	1983	F	P	U	Α
ABRAXUS	AB1	1984	F	L	U	Α
ABRAXUS	AB1	1985	F	Ŭ	U	A
AGASSIZ	AG1	1979	M	U	Ŭ	U
AGASSIZ	AG1	1980	M	Ŭ	ט	U
AGASSIZ	AG1	1981	M	Ŭ	ប	Ü
AGASSIZ	AG1	1982	M	U	U	A
AGASSIZ	AG1	1983	M	U	Ŭ	A
AGASSIZ	AG1	1984	M	U	ប	A
AGASSIZ	AG1	1985	M	ប	Ŭ	A
ALPHORN	AL3	1984	M	Ŭ	1	J
ALPHORN	AL3	1985	M	U	2	J
ALTIPLANA	AL1	1979	F	U	U	U
ALTIPLANA	AL1	1980	F	Ŭ	Ū	U
ALTIPLANA	AL1	1981	F	Ŭ	U	Α
ALTIPLANA	AL1	1982	F	U	U	Α
ALTIPLANA	AL1	1983	F	Ŭ	U	A
ALTIPLANA	AL1	1984	F	P	U	Α
ALTIPLANA	AL1	1985	F	${f L}$	U	Α
ANCHOR	AN1	1984	F	Ŭ	1	J
ANCHOR	AN1	1985	F	U	2	J
APALOOSA	AP2	1983	F	Ū.	U	ប
APALOOSA	AP2	1984	F	U	U	บ
APALOOSA	AP2	1985	F	U	U	U
APEX	AP1	1982	F	P	U	A
APEX	AP1	1983	F	${f L}$	U	A
APEX	AP1	1984	F	Ü	U	A
APEX	AP1	1985	F	U	U	A
ARC	AR5	1984	F	U	U	บ
ARC	AR5	1985	F	U	U	U
ARROW	AR2	1981	F	Ü	U	U
ARROW	AR2	1982	F	U	U	U
ARROW	AR2	1984	F	P	U	A
ARROW	AR2	1985	F	L	U	A
ASE	AS1	1983	F	Ū	U	U
ASE	AS1	1984	F	U	Ū	U
ASE	AS1	1985	F	U	U	Ū
AURORA	AU1	1983	F	υ	1	J
ВАЈА	BA4	1983	F	U	U	ប
BAJA	BA4	1984	F	υ	U	ט
BAJA	BA4	1985	F	U	Ŭ	ប
BATIK	BA3	1984	F	ប	1	J

				RNPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
BATIK	BA3	1985	F	U	2	J
BELTANE	BE1	1981	F	U	1	J
BELTANE	BE1	1982	F	U	2	J
BELTANE	BE1	1983	F	U	3	J
BELTANE	BE1	1984	F	P	4	A
BELTANE	BE1	1985	F	${f L}$	5	A
BINOC	BI2	1980	F	Ŭ	ប	U
BINOC	BI2	1981	F	Ŭ	ប	Ū
BINOC	BI2	1982	F	Ŭ	ซ	Ū
BINOC	BI2	1983	F	P	Ŭ	A
BINOC	BI2	1984	F	${f L}$	Ŭ	A
BINOC	BI2	1985	F	U	ប	A
BISLASH	BI1	1979	F	U	Ū	U
BISLASH	BI1	1980	F	U	Ŭ	U
BISLASH	BI1	1981	F	U	Ŭ	A
BISLASH	BI1	1982	F	U	Ū	A
BISLASH	BI1	1983	F	Ū	ប	A
BISLASH	BI1	1984	F	U	ប	A
BISLASH	BI1	1985	F	U	Ū	A
BUCKSHOT	BU2	1979	F	U	U	U
BUCKSHOT	BU2	1981	F	Ŭ	Ū	Ū
BUCKSHOT	BU2	1982	F	υ	บ	A
BUCKSHOT	BU2	1984	F	U	Ŭ	A
BUCKSHOT	BU2	1985	F	P	U	A
CARDHU	CA4	1981	F	P	U	A
CARDHU	CA4	1982	F	L	ប	A
CARDHU	CA4	1983	F	Ü	U	A
CARDHU	CA4	1984	F	P	U	A
CARDHU	CA4	1985	F	L	U	A
CATSPAW	CA5	1982	F	L	U	A
CATSPAW	CA5	1983	F	P	Ū	A
CATSPAW	CA5	1984	F	L	U	A
CATSPAW	CA5	1985	F	บื	Ŭ	A
CHECK	CH2	1984	M	Ŭ	Ū	Ū
CHECK	CH2	1985	M	Ū	Ū	บั
CHIMES	CH3	1984	F	Ū	Ū	Ū
CHIMES	CH3	1985	F	Ū	Ŭ	Ū
CHURCHILL	CH1	1979	M	Ŭ	Ŭ	Ū
CHURCHILL	CH1	1980	M	Ŭ	บั	Ū
CHURCHILL	CH1	1981	M	Ŭ	บั	บั
CHURCHILL	CH1	1982	M	Ŭ	ប	A
CHURCHILL	CH1	1983	M	Ū	บั	A
CHURCHILL	CH1	1984	M	บั	Ū	A
CHURCHILL	CH1	1985	M	Ü	บั	Ä
CLIPPER	CL5	1983	F	Ü	ΰ	Ü
CLIPPER	CL5	1984	F	Ü	Ü	Ü
CLIPPER	CL5	1985	F	บ	Ü	Ü
	<del>-</del>		•	5	v	J

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
CLOUD	CL2	1980	M	U	3	J
CLOUD	CL2	1981	M	Ŭ	4	A
CLOUD	CL2	1982	M	U	5	A
CLOUD	CL2	1983	M	Ŭ	6	A
CLOUD	CL2	1984	M	U	7	A
CLOUD	CL2	1985	M	U	8	A
CODA	C07	1984	${f F}$	Ū	1	J
CODA	C07	1985	F	ប	2	J
COLT	CO5	1982	M	U	1	J
COLT	CO5	1983	M	Ū	2	J
COLT	CO5	1984	M	Ū	3	Ĵ
COLT	CO5	1985	M	Ū	4	A
COLUMBIA	CO3	1980	F	U	U	Ū
COLUMBIA	CO3	1981	F	U	U	Ū
COLUMBIA	CO3	1982	F	U	U	Ū
COLUMBIA	CO3	1983	F	P	Ü	Ä
COLUMEIA	CO3	1984	F	L	Ū	A
COLUMBIA	CO3	1985	F	U	Ū	A
COMET	CO4	1981	M	Ū	Ū	A
COMET	CO4	1982	M	Ū	Ū	A
COMET	CO4	1983	M	Ū	Ŭ	A
COMET	CO4	1984	M	טֿ	Ū	A
COMET	CO4	1985	M	Ū	Ū	A
COMPASS	C10	1984	F	U	บ	บ
COMPASS	C10	1985	F	บ	Ū	บ
COUGAR	CO9	1983	F	Ŭ	Ü	ΰ
COUGAR	CO9	1984	F	Ū	Ū	Ü
COUGAR	CO9	1985	F	Ŭ	Ŭ	Ü
COVE	C06	1982	M	ซ	Ŭ	Ŭ
COVE	C06	1983	M	Ū	บั	Ü
COVE	CO6	1984	M	Ŭ	บั	บ
COVE	CO6	1985	M	Ŭ	บั	A
CROWN	CR3	1983	F	Ŭ	บ	บิ
CROWN	CR3	1984	F	Ū	Ü	บั
CROWN	CR3	1985	F	Ŭ	Ŭ	บ
CRYSTAL	CR1	1982	M	Ŭ	2	J
CRYSTAL	CR1	1983	M	บั	3	J
CRYSTAL	CR1	1984	M	Ŭ	4	J
CRYSTAL	CR1	1985	M	บั	5	A
CYGNUS	CY1	1980	M	Ü	ซ	U
CYGNUS	CY1	1981	M	Ü	บ	บ
CYGNUS	CY1	1982	M	Ü	ŭ	A
CYGNUS	CY1	1983	M	Ü	Ü	
CYGNUS	CY1	1984	M	ប	บ	A
CYGNUS	CY1	1985	M	บ	ŭ	A
DIAMOND	DI3	1984	M	U		A
DIAMOND	DI3	1985	M		Ü	U
TIMONU	U.L.J	TOOD	М	U	U	U

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
DIGIT	DI1	1980	M	U	ט	บ
DIGIT	DI1	1981	M	Ū	บั	Ū
DIGIT	DI1	1982	M	Ū	บ	Ü
DIGIT	DI1	1983	M	Ū	Ū	Ä
DIGIT	DI1	1984	M	Ŭ	Ŭ	A
DIGIT	DI1	1985	M	Ū	บั	A
EBONY	EB1	1981	F	ับ	ប៊	บ
EBONY	EB1	1982	F	P	ับ	Ā
EBONY	EB1	1983	F	Ĺ	Ŭ	A
EBONY	EB1	1984	F	L?	์ บ	A
EBONY	EB1	1985	F	P	Ū	A
EIDER	EI1	1983	F	P	บ	A
EIDER	EI1	1984	F	Ĺ	Ū	A
EMBER	EM1	1983	M	Ū	1	J
EMBER	EM1	1984	M	Ū	2	Ĵ
EMBER	EM1	1985	M	Ū	3	J
EPAULET	EP1	1981	F	Ū	1	J
EPAULET	EP1	1982	F	Ŭ	2	J
EQUUS	EQ1	1979	F	Ĺ	Ü	Ā
EQUUS	EQ1	1980	F	P	Ŭ	A
EQUUS	EQ1	1981	F	Ĺ	Ū	A
EQUUS	EQ1	1982	F	Ŭ	Ū	A
EQUUS	EQ1	1983	F	P	Ū	A
EQUUS	EQI	1984	F	Ĺ	บ	A
EQUUS	EQ1	1985	F	P	บ	A
FALCO	FA1	1979	F	P	Ŭ	A
FALCO	FA1	1980	F	L	Ū	A
FALCO	FA1	1981	F	Ü	Ŭ	A
FALCO	FA1	1982	F	Ü	Ŭ	A
FALCO	FA1	1983	F	P	Ū	A
FALCO	FA1	1984	F	Ĺ	Ŭ	A
FALCO	FA1	1985	F	P	Ŭ	A
FEATHER	FE1	1979	F	L	Ŭ	A
FEATHER	FE1	1980	F	P	Ū	A
FEATHER	FE1	1981	F	_ L	Ŭ	A
FEATHER	FE1	1982	F	Ū	บั	A
FERN	FE3	1983	F	บั	บั	Ü
FERN	FE3	1984	F	Ŭ	Ü	Ü
FERN	FE3	1985	F	Ŭ	Ū	Ŭ
FLAG	FL1	1981	F	P	Ū	A
FLAG	FL1	1982	F	Ĺ	Ū	A
FLAG	FL1	1984	F	P	บั	A
FLAG	FL1	1985	F	Ĺ	Ŭ	Ä
FLAME	FL2	1982	M	บี	Ŭ	บี
FLAME	FL2	1983	M	Ŭ	Ŭ	A
FLAME	FL2	1984	M	Ü	Ŭ	Ä
FLAME	FL2	1985	M	บ	Ŭ	A
_ <del></del>	<b>-</b>		**	J	•	A

				REPRO		<b>ፓ</b> ሀሃ/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
FRINGE	FR1	1979	${f F}$	${f L}$	Ŭ	A
FRINGE	FR1	1980	F	L?	U	A
FRINGE	FR1	1981	F	P	U	A
FRINGE	FR1	1982	F	L	ប	A
FRINGE	FR1	1983	F	P	U	Α
FRINGE	FR1	1984	F	L	U	A
FRINGE	FR1	1985	F	P	U	A
GLO	GL2	1984	F	U	บ	Ū
GLO	GL2	1985	${f F}$	Ū	U	U
HACHE	HA5	1983	F	U	บ	ប
HACHE	HA5	1984	F	U	U	Ū
HACHE	HA5	1985	F	U	Ū	Ū
HALOS	HA4	1984	M	υ	1	Ĵ
HALOS	HA4	1985	M	U	2	J
HELIX	HE2	1984	M	Ū	บ	Ŭ
HELIX	HE2	1985	М	Ū	Ŭ	Ŭ
IBIS	IB1	1980	F	Ū	ì	J
IBIS	IB1	1981	F	Ū	2	Ĵ
IBIS	IB1	1982	F	Ū	3	J
IBIS	IB1	1983	F	บ	4	A
IBIS	IB1	1984	F	ប៊	5	A
IBIS	IB1	1985	F	P	6	A
IRIS	IR1	1984	M	Ū	ı	J
IRIS	IR1	1985	M	Ū	2	J
ISTAR	IS1	1979	F	Ĺ	บ	A
ISTAR	IS1	1980	F	P	Ŭ	A
ISTAR	IS1	1981	F	Ĺ	Ü	A
ISTAR	IS1	1982	F	บี	Ŭ	A
ISTAR	IS1	1983	F	P	Ŭ	A
ISTAR	IS1	1984	F	Ĺ	Ŭ	A
ISTAR	IS1	1985	F	P	Ŭ	A
IVEE	IV2	1984	F	Ū	Ü	บ
IVEE	IV2	1985	F	ט	Ü	บ
IVORY	IV1	1979	F	Ŭ	บ	ซ
IVORY	IV1	1980	F	. ם	Ü	
IVORY	IV1	1981	F	ט	บ	U U
IVORY	IV1	1982				_
IVORY	IV1	1983	F F	P	Ŭ	A
IVORY	IV1	1984		L	U	A
IVORY	IV1		F	P	U	A
JANUS	JA1	1985	F	L	ŭ	A
JANUS		1981	F	P	U	A
	JA1	1982	F	Ē	Ŭ	A
JANUS	JA1	1983	F	P -	ָּט	A
JANUS	JA1	1984	F	Ē	Ŭ	A
JANUS	JA1	1985	F	P	<b>U</b>	A
KOHOUTEK	KO1	1983	M	U	Ŭ	U
KOHOUTEK	KO1	1984	M	U	U	A

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
KOHOUTEK	KO1	1985	M	U	Ŭ	A
LACE	LA2	1980	F	Ŭ	Ŭ	ប
LACE	LA2	1982	F	U	U	U
LACE	LA2	1983	F	U	U	A
LACE	LA2	1984	F	U	Ŭ	Α
LACE	LA2	1985	F	Ŭ	U	A
LAMBDA	LA3	1982	M	U	U	U
LAMBDA	LA3	1984	M	U	υ	A
LAMBDA	LA3	1985	M	U	U	A
LANCE	LA4	1983	M	U	1	J
LANCE	LA4	1985	M	U	3	J
LEUKOS	LE1	1983	F	Ŭ	U	บ
LEUKOS	LE1	1984	$\mathbf{F}$	U	U	U
LEUKOS	LE1	1985	F	U	U	A
LIGHTNING	LI1	1979	F	U	U	U
LIGHTNING	LI1	1980	F	U	U	A
LIGHTNING	LI1	1981	F	U	U	A
LIGHTNING	LI1	1982	F	U	Ū	A
LIGHTNING	LI1	1984	F	P	U	A
LIGHTNING	LI1	1985	F	L	U	A
LINER	LI3	1981	F	U	U	U
INER	LI3	1982	F	U	U	ប
LINER	LI3	1983	F	U	ប	U
LINER	LI3	1984	${f F}$	U	U	A
LINER	LI3	1985	${f F}$	P	U	A
LITTLE SPOT	LI2	1981	M	Ū	2	J
LITTLE SPOT	LI2	1982	M	U	3	J
LITTLE SPOT	LI2	1983	M	U	4	A
LITTLE SPOT	LI2	1984	M	Ü	5	A
LITTLE SPOT	LI2	1985	M	Ü	6	A
MARS	MA1	1979	F	U	บ	U
MARS	MA1	1980	F	U	ΰ	U
MARS	MA1	1981	${f F}$	P	U	A
MARS	MA1	1982	F	${f L}$	U	A
MARS	MA1	1983	${f F}$	P	U	A
MARS	MA1	1984	${f F}$	LP	U	A
MARS	MA1	1985	$\mathbf{F}$	L	U	A
METEOR	ME1	1981	M	U	U	Ū
METEOR	ME1	1982	M	ซ	U	U
METEOR	ME1	1983	M	ซ	U	A
METEOR	ME1	1984	M	U	U	A
METEOR	ME1	1985	M	U	U	A
MIDNIGHT	MI2	1979	F	U	U	U
MIDNIGHT	MI2	1980	F	U	U	ប
MIDNIGHT	MI2	1981	F	U	Ŭ	Ū
MIDNIGHT	MI2	1982	F	U	U	A
MIDNIGHT	MI2	1983	F	U	U	A

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
MIDNIGHT	MI2	1984	F	U	บ	A
MIDNIGHT	MI2	1985	F	P	Ŭ	A
MIRROR	MI1	1980	M	U	U	U
MIRROR	MI1	1981	M	Ŭ	U	U
MIRROR	MI1	1982	M	บ	U	U
MIRROR	MI1	1983	M	Ŭ	U	Α
MIRROR	MI1	1984	M	U	U	A
MIRROR	MI1	1985	M	U	U	A
MURAL	MU1	1980	F	ט	U	U
MURAL	MU1	1982	F	Ŭ	ซ	U
MURAL	MU1	1984	F	U	U	Α
NEW MOON	NE1	1982	M	Ū	U	บ
NEW MOON	NE1	1983	M	U	U	บ
NEW MOON	NE1	1984	M	Ŭ	U	U
NEW MOON	NE1	1985	M	Ū	บ	A
NOTCH	NO1	1981	M	Ŭ	ซ	ប
NOTCH	NO1	1982	M	บั	U	A
NOTCH	NO1	1983	M	Ū	U	A
NOTCH	NO1	1984	M	U	U	A
NURSE	NU1	1979	F	P	Ū	A
NURSE	NU1	1980	F	L	Ū	A
NURSE	NU1	1981	F	L?	Ū	A
NURSE	NU1	1982	F	P	Ū	A
NURSE	NU1	1983	F	Ĺ	Ŭ	A
NURSE	NU1	1984	F	P	Ū	A
NURSE	NU1	1985	F	Ĺ	Ū	A
OLYMPIA	OL1	1979	F	Ū	Ū	Ü
OLYMPIA	OL1	1980	F	Ŭ	์ บั	Ŭ
OLYMPIA	OL1	1981	F	Ŭ	Ü	Ŭ
OLYMPIA	OL1	1982	F	P	Ŭ	À
OLYMPIA	OL1	1983	F	L	Ü	A
OLYMPIA	OL1	1984	F	P	Ŭ	A
OLYMPIA	OL1	1985	F	L L	Ŭ	A
ONYX	ON1	1980	F	บี	Ŭ	ົົບ
ONYX	ON1	1981	F	บั	Ü	Ü
ONYX	ON1	1982	F	ŭ	Ü	Ü
ONYX	ON1	1984	F	บั	Ŭ	A
ONYX	ON1	1985	r	Ŭ	Ü	À
CRBIT	OR1	1979	Ŧ	บั	Ŭ	A
ORBIT	OR1	1980	F	Ŭ	Ŭ	<b>บ</b> ี
ORBIT	OR1	1981	F	บั	บ	ซ
ORBIT	OR1	1982	F	Ü	Ü	A
ORBIT	OR1	1983	F	P	บ	
ORBIT	OR1	1984	F	L L	Ü	A
ORBIT	OR1	1985	F	P P		A
ORION	OR1	1979			U	A
ORION	OR2	1980	M M	Ŭ	U	ש
OV.T.014	ORZ	1200	II	υ	U	ប

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
ORION	OR2	1981	M	U	U	U
ORION	OR2	1982	M	Ŭ	U	A
ORION	OR2	1983	M	U	U	A
ORION	OR2	1984	M	Ū	U	A
ORION	OR2	1984	M	U	U	A
OTHELLO	OT1	1979	M	Ū	U	บ
OTHELLO	OT1	1980	M	Ŭ	Ū	บ
OTHELLO	OT1	1981	M	ប៊	U	A
OTHELLO	OT1	1982	M	U	U	A
OTHELLO	OT1	1983	M	Ū	U	A
OTHELLO	OT1	1984	M	Ū	บ	A
OTHELLO	OT1	1985	M	U	U	A
PATCHES	PA2	1980	М	U	U	บ
PATCHES	PA2	1981	M	U	ซ	บ
PATCHES	PA2	1982	M	ซ	U	บ
PATCHES	PA2	1983	M	Ŭ	U	Ā
PATCHES	PA2	1984	M	U	U	A
PATCHES	PA2	1985	M	Ū	Ū	A
PEGASUS	PE2	1979	F	Σ.	Ū	A
PEGASUS	PE2	1981	F	P	Ŭ	A
PEGASUS	PE2	1982	F	L	ซ	A
PEGASUS	PE2	1983	F	Ū	Ŭ	A
PEGASUS	PE2	1984	F	P	บั	A
PEGASUS	PE2	1985	F	L	Ū	A
PEPPER	PE1	1980	F	Ū	บ	Ü
PEPPER	PE1	1981	F	P	Ŭ	A
PEPPER	PE1	1982	F	- L	Ŭ	A
PEPPER	PE1	1983	F	ซื	บั	A
PEPPER	PE1	1984	F	ប៊	ប៊	A
PEPPER	PE1	1985	F	P	Ŭ	A
PETRA	PE3	1979	F	Ū	บ	บิ
PETRA	PE3	1982	F	Ü	Ü	A
PETRA	PE3	1984	F	Ü	Ü	Ä
PI	PI2	1984	F	บั	Ü	ີ້ນ
PI	PI2	1985	F	Ü	ซ	บ
POINT	PO2	1979	F	Ü	Ü	ซ
POINT	PO2	1980	F	Ü	บ	บ
POINT	PO2	1981	F	Ü	ប	บ
POINT	PO2	1982	F	Ü	Ü	
POINT	PO2	1983	F	Ü	บ	A
POINT	PO2	1984	F	P	U	A
POINT	PO2	1985	F			A
POLARIS	PO2 PO4	1985	r F	L	Ŭ	A
POLARIS	PO4 PO4	1984	F	U	U	U
QUOTE				Ŭ	U	U
••	QU3	1984	M Sa	Ŭ	Ŭ	U
QUOTE	QU3	1985	<b>⅓</b> ₹7	Ŭ	ប	<u>U</u>
RAVEN	RA3	198:	**	υ	U	U

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
RAVEN	RA3	1984	F	บ	Ū	A
RAVEN	RA3	1985	F	U	U	A
REGULUS	RE1	1984	M	U	1	J
REGULUS	RE1	1985	M	U	2	J
ROPE	RO1	1981	M	U	U	U
ROPE	RO1	1982	M	U	U	Ū
ROPE	RO1	1983	M	U	U	U
ROPE	RO1	1984	M	U	U	A
ROPE	RO1	1985	M	U	U	Α
RUNE	RU1	1980	F	U	U	U
RUNE	RU1	1981	F	U	บ	U
RUNE	RU1	1982	F	P	U	A
RUNE	RU1	1983	F	${f L}$	ΰ	A
RUNE	RU1	1984	F	P	ប	A
RUNE	RU1	1985	F	L	U	A
SALT	SA1	1979	F	P	Ū	A
SALT	SA1	1980	F	Ĺ	Ū	A
SALT	SA1	1981	F	Ū	Ü	A
SALT	SA1	1982	F	P	Ū	A
SALT	SA1	1983	F	L	Ū	A
SALT	SA1	1984	F	P	Ū	A
SALT	SA1	1985	F	_ L	Ū	A
SCISSORS	SC4	1983	F	บื	Ŭ	Ū
SCISSORS	SC4	1984	F	Ū	Ū	Ū
SCISSORS	SC4	1985	F	Ū	Ū	Ŭ
SCRATCH	SC1	1979	F	Ū	Ū	Ŭ
SCRATCH	SC1	1980	F	Ŭ	Ū	Ŭ
SCRATCH	SC1	1981	F	Ū	Ū	Ū
SCRATCH	SC1	1982	F	Ū	Ū	Ä
SCRATCH	SC1	1983	F	บั	Ü	A
SCRATCH	SC1	1984	F	P	Ü	A
SCRATCH	SC1	1985	F	Ĺ	Ü	A
SCYLLA	SC2	1982	F	Ü	1	Ĵ
SCYLLA	SC2	1983	F	บ	2	J
SCYLLA	SC2	1984	F	บั	3	J
SCYLLA	SC2	1985	F	บั	4	J
SCYTHE	SC3	1982	M	Ü	3	J
SCYTHE	SC3	1983	M	Ü	4	A
SCYTHE	SC3	1984	M	Ü	5	A
SCYTHE	SC3	1984	M	Ŭ	6	A
SEAL	SE3	1984	M	ซ	1	д J
SEAL	SE3	1985	M	Ŭ	2	J
SHARK	SH2	1984	F	Ü	Ü	
SHARK	SH2	1985	r F	U U	U	U
SICKLE	SH2 SI1	1985	r F			U
SICKLE	SII SII			U	Ŭ	U
SICKLE		1981	F	U	Ŭ	U
SICVID	SI1	1982	F	Ū	U	A

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
SICKLE	SI1	1983	F	U	U	A
SICKLE	SI1	1984	F	ប	Ŭ	A
SICKLE	SI1	1985	F	P	បី	A
SILVER	SI2	1979	F	P	บั	A
SILVER	SI2	1980	F	L	บั	A
SILVER	SI2	1981	F	บี	บั	A
SILVER	SI2	1982	F	P	បី	A
SILVER	SI2	1983	F	Ĺ	บั	A
SILVER	SI2	1984	F	P	บั	A
SILVER	SI2	1985	F	Ĺ	Ü	A
SINESTRA	SI3	1979	F	บี	บั	Ü
SINESTRA	SI3	1980	F	P	Ŭ	A
SINESTRA	SI3	1981	F	Ĺ	บั	A
SINESTRA	SI3	1982	F	P	Ŭ	A
SINESTRA	SI3	1983	F	Ĺ	Ŭ	บ
SINESTRA	SI3	1984	F	บี	บั	Ä
SINESTRA	SI3	1985	F	P	บั	A
SIRIUS	SI4	1983	M	Ū	1	J
SIRIUS	SI4	1984	M	Ŭ	2	J
SIRIUS	SI4	1985	M	Ü	3	J
SLINGSHOT	SL2	1983	M	Ŭ	1	J
SLINGSHOT	SL2	1984	M	Ü	2	J
SLINGSHOT	SL2	1985	M	Ü	3	J
SOCKEYE	SO3	1984	M	Ŭ	Ū	Ū
SOCKEYE	\$03	1985	M	Ü	Ü	Ū
SOD	S01	1979	F	บ	Ŭ	Ü
SOD	SO1	1980	F	Ü	Ü	Ü
SOD	S01	1981	F	Ŭ	Ŭ	บี
SOD	S01	1982	F	Ŭ	Ŭ	A
SOD	\$01 \$01	1983	F	Ü	Ü	Ä
SOD	S01	1984	F	P	Ŭ	Ä
SOD	SO1	1985	F	Ĺ	Ü	A
SPEAR	S2P	1985	M	מ	1	Ĵ
SPECKLES	SP3	1981	M	Ŭ	Ü	บ
SPECKLES	SP3	1982	M	Ü	Ü	Ü
SPECKLES	SP3	1983	M	บ	บ	บ
SPECKLES	SP3	1984	M	Ü	Ü	A
SPECKLES	SP3	1985	M	Ü	ซ	Ā
SPLINTER	SIP	1985	F	Ü	1	Ĵ
SPOON	SP1	1979	F	บ	บั	U
SPOON	SP1	1980	F	Ū	Ü	Ū
SPOON	SP1	1981	F	Ü	Ū	A
SPOON	SP1	1982	F	P	ប	A
SPOON	SP1	1983	r F	L L	บ	A A
SPOON	SP1	1984	F	U	ซ	A
SPOON	SP1	1985	r F	ŭ		
STRIPES	ST7				U	A
SIKILES	517	1984	M	U	ប	U

				REPRO		JUV/
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT
STRIPES	ST7	1985	M	Ŭ	U	บ
STUB	ST1	1979	M	Ŭ	U	U
STUB	ST1	1980	M	U	U	U
STUB	ST1	1981	M	U	U	U
STUB	ST1	1982	M	U	Ū	A
STUB	ST1	1983	M	U	U	A
STUB	ST1	1984	M	Ŭ	U	A
STUB	ST1	1985	M	U	U	A
SWORD	SW1	1985	M	U	1	J
TALON	TA2	1982	F	U	1	J
TALON	TA2	1983	F	U	2	J
TALON	TA2	1984	F	U	3	J
TALON	TA2	1985	F	U	4	A
TANITH	TA3	1982	F	U	2	J
TANITH	TA3	1983	F	U	3	J
TANITH	TA3	1984	F	Ŭ	4	A
TANITH	TA3	1985	F	Ŭ	5	A
TASSLE	TA1	1981	M	U	2	J
TASSLE	TA1	1982	M	U	3	J
TASSLE	TA1	1983	M	บ	4	A
TASSLE	TA1	1984	M	U	5	A
TASSLE	TA1	1985	M	ប	6	Ā
THORN	TH3	1985	M	U	2	J
TIARA	TI2	1984	M	Ū	ī	J
TIARA	TI2	1985	M	Ū	2	Ĵ
TRIDENT	TR4	1983	F	บั	1	J
TRIDENT	TR4	1984	F	Ü	2	Ĵ
TRIDENT	TR4	1985	F	บั	3	J
TRINE	TR5	1981	F	P	Ŭ	A
TRINE	TR5	1982	F	Ĺ	Ü	A
TRINE	TR5	1983	F	P	Ŭ	A
TRINE	TR5	1984	F	Ĺ	Ü	A
TRINE	TR5	1985	F	P	Ŭ	A
TRITON	TR3	1981	M	Ü	บ	Ū
TRITON	TR3	1982	M	Ŭ	บ	Ü
TRITON	TR3	1983	M	Ŭ	บ	Ü
TRITON	TR3	1984	M	Ü	ซ	A
TRITON	TR3	1985	M	Ü	บ	A
TRUNK	TR2	1979	M	Ü	Ü	
TRUNK	TR2	1980	M	ซ		A
TRUNK	TR2	1981			U	A
		1981	M	ŭ	ט	A
TRUNK	TR2		M	U T	U	A
TRUNK	TR2	1983	M	U	U	A
TRUNK	TR2	1984	M	ប	U	A
TRUNK	TR2	1985	M	Ŭ	U	A
TUSK	TU1	1980	M	Ŭ	1	J
TUSK	TUI	1981	M	U	2	J

				REPRO		JUV/	
WHALE	CODE	YEAR	GENDER	STATUS	AGE	ADULT	
TUSK	TU1	1982	M	Ü	3	J	
TUSK	TU1	1983	M	U	4	A	
TUSK	TUl	1984	M	U	5	A	
TUSK	TU1	1985	M	U	6	A	
VEIL	VE3	1982	F	P	Ŭ	A	
VEIL	VE3	1983	F	L	U	A	
VEIL	VE3	1984	F	P	ប	A	
VEIL	VE3	1985	F	L	U	A	
WALRUS	WA3	1984	M	U	U	บ	
WALRUS	WA1	1985	M	U	Ŭ	A	
WARRIOR	WA1	1982	${f F}$	U	ប	A	
WARRIOR	WA1	1983	F	Þ	U	A	
WARRIOR	WA1	1984	F	L	U	A	
WARRIOR	WA1	1985	F	P	U	A	
ZEBRA	ZE1	1984	${f F}$	U	U	บ	
ZEBRA	ZE1	1985	F	U	บ	ប	

#### APPENDIX II

# Data set

INDCODE: Computer code for each individual humpback whale.

GENDER: Male or female.

REPSTAT: Reproductive status of females, pregnant or lactating, when known.

FLUCOL: Fluke coloration ranging from 1 - 5 (Figure 2.5).

PARSCAR: Presence or absence of parallel scars on flukes.

ARRIVE: Day of first observed sighting in study area.

DEPART: Day of last observed sighting in study area.

RESIDE: Number of days between arrival and departure.

SOUTH: Observed presence on the breeding grounds earlier that year.

LOGDIS: Log of the greatest observed distance an individual was identified from the centroid of its Stellwagen range.

AGE: Age in years of all individuals observed as calves in previous years.

CJA: Calf, juvenile or adult.

RELDIS: The average distance of the individual from the centroid of positions of all animals sighted that year.

MEANGRP: The mean group size of all associations.

NBDATAV: Near-boat/numobs(number of observations)

LTAILAV: Lobtail/numobs

SURFEDAV: Feeding/numobs

SPYHOPAV: Spyhoping/numobs

BREACHAV: Breaching/numobs

LOGAV: Resting/numobs

FLIPAV: Flipping/numobs

SOCIOAV: Social/sociobs

LRELDIS: Log reldis

LMEANGRP: Log meangrp

LNBDATAV: Log nbdatav

LLTAILAV: Log ltailav

LSURFEDAV: Log surfedav

LSPYHOPAV: Log spyhopav

LBREACHAV: Log breachav

LLOGAV: Log logav

LFLIPAV: Log flipav

LSOCIALAV: Log socialav

LARRIVE: Log arrive

LDEPART:Log depart

LRESIDE: Log reside

#### REFERENCES

- Alexander, R. D. 1974. The evolution of social behavior. Ann. Rev. Ecol. Syst. 5:325-383.
- Armitage, K. B. 1981. Sociality as a life history tactic of ground squirrels. Oecol. (Berl) 37:257-272.
- Armitage, K. B. 1986. Marmot polygyny revisited: Determinants of male and female reproductive strategies. In: Ecological aspects of social evolution, D. I. Rubenstein and R. W. Wrangham (eds.). Princeton University Press, Princeton, New Jersey. pp:303-331.
- Arnbom, T. and H. Whitehead. 1989. Observations on the composition and behavior of groups of female sperm whales near the Galapagos Islands. Can. J. Zool. 67: 1-7.
- Baker, C. S. and L. M. Herman. 1981. Migration and local movement of humpback whales through Hawaiin waters.Can. J. Zool. 59:460-469.
- Baker, C. S. and L. Herman. 1984. Aggressive behavior between humpback whales (<u>Megaptera novaeangliae</u>) on the Hawaiian wintering grounds. Can. J. Zool. 62: 1922-1937.
- Baker, C. S., Herman, L. M., Bays, B. G. and W. F. Stifel. 1982. Effects of vessel traffic on the behavior of humpback whales in Southeast Alaska. Report to the National Marine Fisheries Service. No. 81-ABC-00114.
- Baker, C. S., Herman, L. M., Perry, A., Lawton, W. S., Straley, J. M. and J. H. Straley. 1985. Population characteristics and migration of summer and late-season humpback whales (Megaptera novaeangliae) in Southeastern Alaska. Mar. Mamm. Sci. 1(4):304-323.
- Baker, C. S., Herman, L. M., Perry, A., Lawton, W. S., Straley, J. M., Wolman, A. A., Kaufman, G. D., Winn, H. E., Hall, J. D., Reinke, J. M. and J. Ostman. 1986. Migratory movement and population structure of humpback whales (Megaptera novaeangliae) in the central and eastern North Pacific. Mar. Ecol. 31:105-119.

- Balcomb, K. C. and G. Nichols. 1982. Humpback whale census in the West Indies. Rep. Int. Whal. Comm. 32:401-406.
- Balcomb, K. C., Boran, J. R., Osborne, R. W. and N. J. Haenel. 1980. Observations of killer whales (Orcinus orca) in Greater Puget Sound, State of Washington. U. S. Dept. Commer. NTIS Pb90-224728.
- Beale, T. 1893. The natural history of the sperm whale. Holland Press, United Kingdom.
- Bekoff, M., Diamond, J. and J. B. Mitton. 1981. Lifehistory patterns and sociality in Canids: body size, reproduction and behavior. Oecol. (Berl) 50:386-390.
- Bertram, B. C. R. 1975. Social factors influencing reproduction in wild lions. J. Zool. London. 177:463-482.
- Best, P. B. 1979. Social organization in sperm whales,

  <u>Physeter macrocephalus</u>. In: Behavior of marine animals

  Vol. 3, H. E. Winn and B. L. Olla (eds.). Plenum Press,

  New York, New York. pp:227-289.
- Best, P. B. 1982. Seasonal abundance, feeding, reproduction, age and growth in minke whales off Durban (with incidental observations from the Antarctic). Rep. Int. Whal. Commn. 32:759-786.
- Bigg, M. A., Olesiuk, P. F., Ellis, G. M., Ford, J. K. B. and K. C. Balcomb. 1990. Social organization and genealogy of resident killer whales (Orcinus orca) in the coastal waters of British Columbia and Washington state. Rep. Int. Whal. Commn. Special Issue 12:383-405.
- Bogoslovskaya, L. S., Votrogov, L. M. and T. N. Semenova. 1981. Feeding habits of the gray whale off Chukotka. Rep. Int. Whal. Commn. 31:507-510.
- Bogoslovskaya, L. S., Votrogov, L. M. and T. N. Semenova. 1982. Distribution and feeding of the gray whale in the waters of the Chukotka Peninsula in summer and autumn of 1980. Rep. Int. Whal. Commn. 32:385-399.
- Brodie, P. 1968. Bioenergetics and growth. Hafner Publishing Company, New York, New York.
- Brown, S. G. 1976. Sightings of blue and humpback whales on the Icelandic whaling grounds 1969 to 1974. Rept. Int. Whal. Commn. 26:297-299.

- Carlson, C. A. 1982. Pigmentation and scarification of the humpback whale, <u>Megaptera novaeangliae</u>, in the waters off Cape Cod, Massachusetts. <u>Masters Degree</u> Thesis. Bridgewater College, Bridgewater, Massachusetts August, 1982.
- Carlson, C. A., Mayo, C. A. and H. A. Whitehead. 1990. Changes in the ventral fluke pattern of the humpback whale (<u>Megaptera novaeangliae</u>), and its effect on matching; evaluation of its significance to photo-identification research. Rep. Int. Whal. Commn. Special Issue 12:105-111.
- Chabot, D. 1988. A quantitative technique to compare and classify humpback whale (Megaptera novaeangliae) sounds. Ethol. 77(2):89-102.
- Chittleborough, R. G. 1958. The breeding cycle of the female humpback whale. Austr. J. Mar. Freshw. Res. 9:1-13.
- Clapham, P. J. and C. A. Mayo. 1987. Reproduction and recruitment of individually identified humpback whales, Megaptera novaeangliae, observed in Massachusetts Bay, 1979-1985. Can. J. Zool. Vol.65:2853-2863.
- Clapham, P. J. and C. A. Mayo. 1990. Reproduction of humpback whales (<u>Megaptera novaeangliae</u>) observed in the Gulf of Maine. Rep. Int. Whal. Commn. Special Issue 12:171-175.
- Clapham, P. J., Baraff, L. S., Carlson, C. A., Christian, M. A., Mattila, D. K., Mayo, C. A., Murphy, M. A. and S. Pittman. in review. Seasonal occurrence and annual return of humpback whales, <u>Megaptera novaeangliae</u>, in the southern Gulf of Maine.
- Clark, C. W. 1983. Acoustic communication and behavior of the southern right whale (<u>Eubalaena australis</u>). In: Communication and behavior of whales, R. Payne, (ed.). Westview Press, Boulder, Colorado. pp:163-198.
- Clutton-Brock, T. H. 1989. Mammalian mating systems. Proc. R. Soc. Lond. B236:339-372.
- Clutton-Brock, T. H. and P. H. Harvey. 1978. Comparative approaches to investigating adaptation. In:Behavioral ecology:an evolutionary approach, J. R. Krebs and N. B. Davies (eds.) pp:7-29.

- Clutton-Brock, T. H., Guinness, F. E. and S. D. Albon. 1982. Red deer: the behavior and ecology of two sexes. Chicago University Press. Chicago, Illinois.
- Condy, P. R., van Aarde, R. J. and M. N. Bester. 1978.
  The seasonal occurrence and behavior of killer whales
  Orcinus orca, at Marion Island. J. Zool., Lond. 184:
  449-464.
- Cullen, E. 1957. Adaptations of the kittewake to cliff nesting. IBIS. 99:275-302.
- Crook, J. H. 1964. The evolution of social organization and visual communication in the weaver birds (Ploceinae). Beh. Suppl. 10:1-178.
- Dahlheim, M. E. 1986. The acoustic behavior of gray whales, <u>Eschrichtius robustus</u>. Unpbl. PhD Thesis. University of Vancouver, British Columbia.
- Darling, J. D. and C. M. Jurasz. 1983. Migratory destinations of North Pacific humpback whales (Megaptera novaeangliae). In: Communication and behavior of whales, R. Payne (ed.) Westview Press. Boulder, Colorado. pp.359-368.
- Darling, J. D. and H. Morowitz. 1986. Census of Hawaiin humpback whales <u>Megaptera</u> <u>novaeangliae</u> by individual identification. Can. J. Zool. 64(1):105-111.
- Dawbin, W. H. 1966. The seasonal migratory cycle of humpback whales. In: Whales, dolphins and porpoises, K. S. Norris (ed.). University of California Press, Berkley, California. pp:145-170.
- Dolphin, W. F. 1987. Prey densities and foraging of humpback whales, <u>Megaptera novaeangliae</u>. Experientia 43(4): 468-470.
- Donovan, G. P. 1982. Summary report of the research carried out by the **Shonan Maru No. 2**, 12 November-11 December 1982. typescript.
- Dorsey, E. M., Stern, S. J., Hoelzel, A. R. and J. Jacobson. 1990. Minke whales (<u>Balaenoptera acutorostrata</u>) from the west coast of North America: individual recognition and small-scale site fidelity. Rep. Int. Whal. Commn. Special Issue 12:357-348.

- Drickamer, L. C. 1974. A ten-year summary of reproductive data for free-ranging <u>Macaca mulatta</u>. Folia Primatol. 21:61-80.
- D'Vincent, G. C, Nilson, R. M. and F. R. Sharpe. 1989. The behavioral biology of cooperative lunge-feeding hump-back whales (Megaptera novaeangliae) in southeast Alaska. Eighth Biennial Conference on the Biology of Marine Mammals, Pacific Grove, California. (Abstr.)
- Edds, P. L. and J. A. MacFarlane. 1987. Occurrence and general behavior of balaenopterid cetaceans summering in the St. Lawrence estuary, Canada. Can. J. Zool. 65:1363-1376.
- Elgar, M. A., Pagel, M. D. and P. H. Harvey. 1988. Sleep in mammals. Anim. Behav. 36:1407-1419.
- Evans, P. G. H. 1987. The natural history of whales and dolphins. Facts on File Publications, New York, New York.
- Gambell, R. 1968. Seasonal cycles and reproduction in sei whales of the southern hemisphere. Discovery Rep. 35:31-134.
- Gentry, R. L. 1974. The development of social behavior through play in the Stellar sealion. Sci. Amer. 192(1): 62-67.
- Glockner-Ferrari, D. A. 1983. Determining the sex of humpback whales (Megaptera novaeangliae) in their natural environment. In:Communication and behavior of whales, R. Payne (ed.). Westview Press. Boulder, Colorado. pp:228-258.
- Glockner-Ferrari, D. A. and S. C. Venus. 1983. Identification, growth rate and behavior of humpback whale (Megaptera novaeangliae) cows and calves in the waters off Maui, Hawaii, 1977-79. In:Communication and behavior of whales, R. Payne (ed.). Westview Press, Boulder, Colorado. pp:223-258.
- Glockner-Ferrari, D. A. and M. J. Ferrari. 1985. Individual identification, behavior, reproduction and distribution of humpback whales, <u>Megaptera novaeangliae</u> in Hawaii. NTIS Report No. MMC-83/06, Springfield, Virginia.

- Glockner-Ferrari, D. A. and M. J. Ferrari. 1990. Reproduction in the humpback whale (<u>Megaptera novaeangliae</u>) in Hawaiian waters, 1975-1988:the life history, reproductive rates and behavior of known individuals identified through surface and underwater photography. Rep. Int. Whal. Commn. Special Issue 12:161-170.
- Goodale, D. R. 1981. The temporal and geographical distribution of humpback, finback and right whale calves. M. S. Thesis, University of Rhode Island, Kingston, Rhode Island.
- Goodall, J. 1971. In the shadow of man. Houghton Mifflin Company. Boston, Massachusetts.
- Goodall, J. 1988. The chimpanzees of Gombe. Patterns of behavior. The Belknap Press of Harvard University Press. Cambridge, Massachusetts.
- Guinee, L. N., Chu, K. and E. M. Dorsey. 1983. Changes over time in the songs of known individual humpback whales (Megaptera novaeangliae). In:Communication and behavior of whales, R. Payne (ed.). Westview Press, Bolder, Colorado. pp:59-80.
- Hain, J. H. W., Carter, G. R., Kraus, S. D., Mayo, C.A. and H. E. Winn. 1981. Feeding behavior of the humpback whale, <u>Megaptera novaeangliae</u>, in the western North Atlantic. Fish. Bull., U. S. 80(2):259-268.
- Harvey, P. H., Kavanagh, M. and T. H. Clutton-Brock. 1978. Sexual dimorphism in primate teeth. J. Zool. Lond. 186: 475-486.
- Harwood, J. 1990. Whales and seals are individuals. TREE 5(6):171.
- Hays, H. E., Winn, H. E. and R. Petricig. 1985. Anomalous feeding behavior of a humpback whale. J. Mammal. 66(4): 819-821.
- Herman, L. M. and K. C. Antinoja. 1977. Humpback whales in the Hawaiin breeding waters: population and pod characteristics. Sci. Rep. Whales. Res. Inst. 29:59-85.
- Herman, L. M., Forstell, K. H. and K. C. Antinoja. 1980. The 1966/67 migration of humpback whales into Hawaiin waters: composite description. Mar. Mamm. Comm. Rep. MMC-77/79. Washington, D. C.

- Hoelzel, A. R., Dorsey, E. M. and S. J. Stern. 1989. The foraging specializations of individual minke whales. Anim. Behav. 38:786-794.
- Jarman, P. J. 1974. The social organization of antelope in relation to their ecology. Beh. 48:215-267.
- Jarman, P. J. and C. S. Southwell. 1986. Grouping, associations and reproductive strategies in eastern grey kangaroos. In: Ecological aspects of social evolution: birds and mammals, D. I. Rubenstein and R. W. Wrangham (eds.). Princeton University Press, Princeton, New Jersey. pp:399-428.
- Juracz, C. M. and V. P. Jurasz. 1979. Feeding modes of the humpback whale, <u>Megaptera</u> <u>novaeangliae</u>, in Southeast Alaska. Sci. Rep. Whal. Res. Inst., Tokyo 31:69-83.
- Kasamatsu, F. and S. Ohsumi. 1981. Distribution pattern of minke whales in the Antarctic with special reference to sex ratio in the catch. Rep. Int. Whal. Commn. 31: 345-348.
- Katona, S. K. and S. Kraus. 1979. Photographic identification of individual humpback whales (Megaptera novaeangliae): an evaluation and analysis of the technique. Final Report to the U.S. Marine Mammal Commission. 33:345-353.
- Katona, S. K. and H. Whitehead. 1981. Identifying humpback whales using their natural markings. Polar Res. 20(128):439-444.
- Katona, S. K. and J. A. Beard. 1990. Population size, migrations, and feeding aggregations of the humpback whale (Megaptera novaeangliae) in the western North Atlantic Ocean. Rep. Int. Whal. Commn. Special Issue 12:295-305.
- Katona, S. K., Harcourt, P. M., Perkins, J K. and S. Kraus. 1980. Humpback whales in the western North Atlantic: a catalog of identified individuals. 2nd ed. College of the Atlantic. Bar Harbor, Maine.
- Kawai, M. 1965. On the system of social ranks in a natural troop of Japanese monkeys, 1. Basic rank and dependent rank. In: Japanese monkeys, K. Imanishi and S. A. Altman (eds.), Emory University Press, Atlanta, Georgia.

- Kawamura, A. 1970. Food of the sei whale takes by Japanese whaling expeditions in the Antarctic season, 1967-1968. Sci. Rep. Whal. Res. Inst. Tokoyo. 22:127-152.
- Kenney, R. D., Goodale, D. R., Scott, G. P. and H. E. Winn. 1981. Spatial and temporal distribution of humpback whales in the CETAP study area. Chap. 5. In: A characterization of marine mammals and turtles in the Mid- and North Atlantic areas of the U. S. outer continental shelf. Annu. Rep. 1979, Cetacean and Turtle Assessment Program. University of Rhode Island, Bur. Land mange. Contract AA551-CT8-48. U. S. Dep. Int., Washington, DC.
- Koyama, N., Norikoshi, K. and T. Mano. 1975. Population dynamics of Japanese monkeys at Arashiyama. In: Contemporary primatology, M. Kawai, S. Kondo and A. Ehara (eds.). Basel:S. Karger.
- Kraus, S. D. and J. H. Prescott. 1985. A review of the status of right whales (<u>Eubalaena glacialis</u>) in the western North Atlantic: research progress from June 1984-April 1985. Report submitted to World Wildlife Fund-US.
- Kummer, H. 1968. Social organization of hamadryas baboons: a field study. University of Chicago Press, Chicago, Illinois.
- Kummer, H. 1971. Primaye societies: group techniques of ecological adaptation. Aldine-Atherton, Chicago, Illinois.
- Lack, D. 1966. Population studies of birds. Clarendon Press Oxford, England.
- Laws, R. M. 1961. Reproduction, growth and age of southern fin whales. Discovery Rep. 31:327-496.
- Leatherwood, S., Awbrey, F. T. and J. A. Thomas. 1982.
  Minke whale response to a transiting survey vessel. Rep.
  Int. Whal.Commn. 32:795-802.
- Lien, J. and B. Merdsoy. 1979. The humpback is not over the hump. Nat. Hist.88(6):46-49.
- Ljungblad, D. K., Moore, S. E., Clark, J. Y. and J. C.
  Bennett. 1985. Aerial surveys of endangered whales in
  the northern bering, eastern Chukchi, and Alaskan
  Beaufort Seas, 1984: with a six year review, 1974-84.
  Tech. Rep. No. 1046, N.O.S.C., San Diego, California.

- Ljungblad, D. K., Moore, S. E. and D. Rick Van Schoik. 1986. Seasonal patterns of distribution, abundance, migration and behavior of the western Arctic stock of bowhead whales, <u>Balaena mysticetus</u>, in Alaskan Seas. Rep. Int. Whal. Commn. Special Issue 8:177-205.
- Lopez, B. N. 1978. Of wolves and men. Charles Scribner's Sons, New York, New, York.
- Mackintosh, N. A. 1942. The southern stocks of whalebone whales. Disc. Rep. 22:197-300.
- Mackintosh, N.A. 1965. The stocks of whales. Fish. News Books. London, England.
- Madsen, C. J. and L. M. Herman. Social and ecological correlates of cetacean vision and visual appearance. In: Cetacean behavior, L. Herman (ed.). Wiley, New York, New York. pp:101-148.
- Martin, A. R., Katona, S. K., Mattila, D., Hembree, D. and T. D. Waters. 1984. Migration of humpback whales between the Caribbean and Iceland. J. Mammal. 65(2): 330-333.
- Masui, K., Sugiyama, Y., Nishimura, A. and H. Ohsawa. 1975. The life table of Japanese monkeys at Takasakiyama. In: Contemporary primatology, M. Kawai, S. Kondo and H. Ehara (eds.). Basel:S. Karger.
- Matthews, L. H. 1937. The humpback whale, <u>Megaptera</u> nodosa. Disc. Rep. 17:7-92.
- Mattila, D. 1983. Humpback whales off Puerto Rico: population composition and habitat use. Fifth Biennial Conference on the Biology of Marine Mammals, Boston, Massachusetts. (Abstr.)
- Mattila, D. M., Stone, G. S., Katona, S. K. and P. J. Clapham. 1985. Humpback whales on Silver Bank, 1984: population composition and habitat use. In: Abstracts of the Sixth Biennial Conference on the Biology of Marine Mammals, Boston, Massachusetts. Society for Marine Mammology. (Abstr.)
- Mattila, D. M., Guinee, L. N. and C. A. Mayo. 1987. Humpback whale songs on a North Atlantic feeding ground. J. Mammal. 68(4):880-883.

- Mayo, C. A. 1982. Observations of cetaceans: Cape Cod Bay and Stellwagen Bank, Massachusetts 1975-1979. Mar. Mamm. Comm., Nat. Mar. Tech. Info. Serv.
- Mayo, C. A. 1983. Patterns of distribution and occurrence of humpback whales in the southern Gulf of Maine. In: Abstracts of the Fifth Biennial Conference on the Biology of Marine Mammals, Boston, Massachusetts. Society for Marine Mammology. (Abstr.)
- Mayo, C.A., Carlson, C. A., Clapham, P. J. and D. Mattila. 1985. Humpback whales of the southern Gulf of Maine. Shankpainter Printing Company. Provincetown, Massachusetts.
- McCormick, J. G. 1969. Relationship of sleep, respiration and anaesthesia in the porpoise. A preliminary report. Proc. Nat. Acad. Sci. USA 62:697-703.
- Mc Gill, R., Tukey, J. W. and W. A. Larsen. 1978. Variations of box plots. Amer. Stat. 32:12-16.
- McSweeny, D. J., Chu, K. C., Dolphin, W. F. and L. N. Guinee. 1989. North Pacific humpback whale songs: a comparison of Southeast Alaskan feeding ground songs with Hawaiin wintering ground songs. Mar. Mamm. Sci. 5(2):139-148.
- Melville, H. 1851. Moby Dick. Collins, London (1953).
- Mitchell, E. 1974. Trophic relationships and competition for food in northwest Atlantic whales. Can. J. Zool. Ann. Meeting:123-132.
- Mizue, K. 1949. Foods of whales in adjacent waters of Japan. Sci. Rep. Whal. Res. Inst. Tokoyo. 2:81-97.
- Mobley, J. R. and L. M. Herman. 1985. Transience of social affiliations among wintering humpback whales (Megaptera novaeangliae) on the Hawaiin wintering grounds. Can. J. Zool. 63:762-772.
- Mori, A. 1975. Analysis of population changes by measurement of body weight in Koshima troops of Japanese monkeys. Primates 20:371-397.
- Moss, C. J. 1981. Social Circles. Wildl. News 16(1): 2-7.
- Moss, C. J. 1983. Oestrus behavior and remale choice in the African elephant. Behavior 86:167-196.

- Moss, C. J. and J. H. Poole. 1983. Relationships and social structure of African Elephants. In: Primate social relationships, R. A. Hinde (ed.), Blackwell Publications, Oxford, England. pp:315-325.
- Nemoto, T. 1964. School of baleen whales in the feeding areas. Sci. Rep. Whales Res. Inst. Tokyo 18:89-110.
- Norris, K. S., Villa-Ramirez, B., Nichols, G., Wursig, B. and K. Miller. 1983. Lagoon entrance and other aggregations of gray whales (<u>Eschrichtius robustus</u>). In: Communication and behavior of whales, R. Payne (ed.). Westview Press, Boulder, Colorado. pp:259-293.
- Ohsumi, S. 1979. Feeding habits of the minke whale in the Antarctic. Rep. Int. Whal. Commn. 35:473-476.
- Olesiuk, P. F., Bigg, M. A. and G. M. Ellis. 1990. Life history and population dynamics of resident killer whales (<u>Orcinus orca</u>) in the coastal waters of British Columbia and Washington state. Rep. Int. Whal. Commn. Special Issue 12:209-243.
- Payne, K., Tyack, P. and R. Payne. 1983. Progressive changes in the song of humpback whales (Megaptera novaeangliae): a detailed analysis of two seasons in Hawaii. In:Communication and behavior of whales, R. Payne (ed.). Westview Press, Boulder, Colorado. pp:9-57.
- Payne, P. M., Nicolas, J. R., O'Brien, L. and K. D. Powers. 1986. Distribution of the humpback whale, <u>Megaptera Novaeanglae</u>, on Georges Bank and in the Gulf of Maine in relation to densities of the sand eel, <u>Ammodytes americanus</u>. Fish. Bull., U. S. 84:271-277.
- Payne, P. M., Wiley, D. N., Young, S. B., Pittman, S., Clapham, P. J. and J. W. Jossi. 1990. Recent fluctuations in the abundance of baleen whales in the southern Gulf of Maine in relation to changes in prey selection. Fish. Bull., U. S. 88:687-696.
- Payne, R. 1970. Songs of the humpback whale. Capitol Records. ST-620.
- Payne, R. 1990. Behavior of southern right whales (<u>Eubalaena australis</u>). University of Chicago Press, Chicago, Illinois. In press.

- Payne, R. and L. N. Guinee. 1983. Humpback whale (Megaptera novaeangliae) songs as an indicator of stocks. In:Communication and behavior of whales, R. Payne (ed.). Westview Press, Bolder, Colorado. pp:333-358.
- Payne, R., Brazier, O., Dorsey, E. M., Perkins, J. S., Rowntree, V. J. and A. Titus. 1983. External features in southern right whales (<u>Eubalaena australis</u>) and their use in identifying individuals. In: Communication and behavior of whales, R. Payne (ed.). Westview Press, Boulder, Colorado. pp:371-445.
- Payne, R., Rowntree, V., Perkins, J. S., Cook, J. G. and K. Lankester. 1990. Population size, trends and reproductive parameters of right whales (<u>Eubalaena australis</u>) off Peninsula Valdes, Argentina. Rep. Int. Whal. Commn. Special Issue 12271-278.
- Perkins, J. S., Bryant, P. J., Nichols, G. and D. R. Patten. 1982. Humpback whales (Megaptera novaeangliae) off the west coast of Grenland. Can. J. Zool. 60(11): 2921-2930.
- Perkins, J. A., Balcomb, K. C., Nichols, G. and M. DeAvilla. 1984. Abundance and distribution of humpback whales (Megaptera novaeangliae) in west Greenland Waters. Can. J. Fish. Aquat. Sci. 41(3):533-536.
- Perry, A., Baker, C. S. and L. M. Herman. 1990. Population characteristics of individually identified humpback whales in the central and eastern North Pacific: a summary review. Rep. Int. Whal. Commn. Special Issue 12:307-318.
- Poole, J. H. 1987. Elephants in musth, lust. Nat. Hist. 9(II):46-55.
- Poole, J. H. 1989. Mate guarding, reproductive success and female choice in African elephants. Anim. Behav. 37: 842-849.
- Poole, J. H. and C. J. Moss. 1981. Musth in the African elephant, <u>Loxodonta africana</u>. Nat. 292:830-831.
- Pryor, K. 1986. Non-acoustic communicative behavior of the great whales: origins, comparisons and implications for management. Rep. Int. Whal. Commn. Specia Issue 8:89-96.

- Reynolds, V. 1965. Some behavioral comparisons between the chimpanzee and the mountain gorilla in the wild. Amer. Anthropol. 67(3):691-706.
- Rice, D. W. and A. A. Wolman. 1971. The life history and ecology of the gray whale. Amer. Soc. Mammal. Spec. Publ. 3.
- Rubenstein, D. I. 1986. Ecology and sociality in horses and zebras. In: Ecological aspects of social evolution. Birds and Mammals, D. I. Rubenstein and R. W. Wrangham (eds.) pp:282-302.
- Sade, D. S., Cushing, K., Cushing, P., Dunaif, J., Figueroa, A., Kaplan, J. R., Laurer, C., Rhodes, D. and J. Schneider. 1976. Population dynamics in relation to social structure on Cay Santiago. Yrbk. Phys. Anthrop. 20:253-262.
- Scammon, C. M. 1874. Marine mammals of the northwest coast of North America. John H. Carmay and Company, San Francisco, California.
- Schilling, M. R., Weinrich, M. T. and C. R. Belt. 1991. Increase of lobtailing while feeding in humpback whales: spreading of a novel behavior. Ninth Biennial Conference on the Biology of marine Mammals. Chicago, Illinois. (Abstr.)
- Sears, R., Williamson, J. M., Wenzel, F. W., Berube, M., Gendron, D. and P. Jones. 1990. Photographic identification of the blue whale (<u>Balaenoptera musculus</u>) in the Gulf of St. Lawrence, Canada. Rep. Int. Whal. Commn. Special Issue 12:335-342.
- Seipt, I., Carlson, C. and C. A. Mayo. 1984. Sexual composition of humpback whales on Stellwagen Bank. In: Abstracts of The Western North Atlantic Marine Mammal Conference. Boston, Massachusetts. (Abstr.)
- Sigurjonsson, J. and T. Gunnlaugsson. 1990. Recent trends in abundance of blue (<u>Balaenoptera musculus</u>) and humpback whales (<u>Megaptera novaeangliae</u>) off west and southwest Iceland based on systematic sightings records with a note on the occurrence of other cetacean species. Rep. Int. Whal. Commn. 40:537-551.
- Silber, G. K. 1986. The relationship of social vocalizations to surface behavior and aggression in the Hawaain humpback whale (Megaptera novaeangliae). Can. J. Zool. 64(10):2075-2080.

- Swartz, S. L. 1986. Gray whale migratory, social and breeding behavior. Rep. Int. Whal. Commn. Special Issue 8:207-229.
- Tarasevich, M. N. 1967. On the composition of Cetacea groupings. 2. Groupings of fin whales. Zool. Zh. 46(3): 420-431. (In Russian.)
- Thompson, P. O., Cummings, W. C. and S. J. Ha. 1986. Sounds, source levels, and associated behavior of humpback whales, Southeast Alaska. J. Accoust. Soc. Am. 80(3):735-740.
- True, F. W. 1904. The whalebone whales of the western North Atlantic. Smithsonian. Contrib. Knowl. 33.
- Tukey, J. W. 1977. Exploratory data analysis. Addison-Wesley, Reading, Massachusetts.
- Tyack, P. 1982. Humpback whales respond to sounds of their neighbors. Unpbl. PhD Thesis. Rockefeller University, New York.
- Tyack, P. and H. Whitehead. 1983. Male competition in large groups of wintering humpback whales. Behav. 83 (1-2):132-154.
- Vehera, S. 1986. Sex and group differences in feeding on animals by wild chimpanzees in the Mahale Mountains National Park, Tanzania. Prim. 27(7):1-13.
- Walters, R. J. 1989. Transition to adulthood. In:Primate societies. (eds.) pp:358-369.
- Waters, S. and H. Whitehead. 1990. Aerial behavior in sperm whales. Can. J. Zool. 68:2076-2082.
- Watkins, W. A. 1986. Whale reactions to human activities in Cape Cod waters. J. Mar. Mamm. Sci. 2(4):251-262.
- Wells, R. S. and M. D. Scott. 1990. Estimating bottlenose dolphin parameters from individual identification and capture-release techniques. Rep. Int. Whal. Commn. Special Issue 12:407-415.
- Weinrich, M. T. 1983. Observations: the humpback whales of Stellwagen Bank. Whale Research Press, P. O. Box 345, Gloucester, Massachusetts.

- Weinrich, M. T., Belt, C. R., Schilling, M. R. and M. E. Cappellino.. 1985. Humpback whales of the southern Gulf of Maine: recent findings on habitat use, social behavior and feeding patterns. Whale Research Press, P.O. Box 345, Gloucester, Massachusetts.
- Whitehead, H. 1982. Populations of humpback whales in the Northwest Atlantic. Rep. Int. Whal. Comm. 32:345-353.
- Whitehead, H. 1983. Structure and stability of humpback whale groups off Newfoundland. Can. J. Zool. 61:191-1397.
- Whitehead, H. 1985a. Humpback whale breaching. In: Investigations on cetacea, G. Pilleri (ed.). pp:117-155.
- Whitehead, H. 1985b. Why whales leap. Sci. Am. 252(3): 84-93.
- Whitehead, H. and M. Moore. 1982. Distribution and move ments of West Indian humpback whales in winter. Can. J. Zool. 10(9):2203-2211.
- Whitehead, H. and J. E. Cascadden. 1985. Predicting inshore whale abundance-whales and capelin off the Newfoundland coast. Can. J. Fish. Aquat. Sci. 42: 976-981.
- Whitehead, H. and C. Glass. 1985. Orcas (killer whales) attack humpback whales. J. Mamm. 66(1):183-185.
- Whitehead, H., Harcourt, P., Ingham, K. and H. Clark. 1980. The migration of humpback whales past the Bay de Verde Penninsula, Newfoundland during June and July 1978. Can. J. Zool. 58(5):687-692.
- Whitehead, H., Chu, K., Perkins, J., Bryant, P. and G. Nichols. 1983a. Population size, stock identity, and distribution of the humpback whales off west Greenland-summer 1981. Rep. Int. Whal. Commn. 33:497-501.
- Whitehead, H. A., Silver, R. and P. Harcourt. 1983b. The migration of humpback whales along the northeast coast of Newfoundland. Can. J. Zool. 60(9):2173-2179.
- Wiley, R. H. 1974. Evolution of social organization and life history patterns among grouse (<u>Aves: Tetraonidae</u>) Q. Rev. Biol. 49:201-227.

- Wilkinson, L. 1987. SYSTAT: The system for statistics. SYSTAT, Inc., Evanston, Illinois.
- Wilkinson, L. 1988. SYGRAPH: The system for graphics for the PC. SYSTAT, Inc., Evanston, Illinois.
- Winn, H. E. and L. K. Winn. 1978. The song of the humpback whale <u>Megaptera novaeangliae</u> in the West Indies. Mar. Biol. 47:97-114.
- Winn, H. E., Edel, R. K. and A. G. Taruski. 1975. Population estimates of the humpback whale <u>Megaptera</u> novaeangliae in the West Indies by visual and acoustical techniques. J. Fish. Res. Bd. Can. 32(4): 499-505.
- Winn, H. E., Beamish, P. and P. J. Perkins. 1979. Sounds of two entrapped humpback whales <u>Megaptera novaeangliae</u>) in Newfoundland. Mar. Biol. 55(2):151-155.
- Winn, H. E., Thompson, T. J., Cummings, W. C., Hain, J., Hudnall, J., Hays, H. and W. W. Steiner. 1981. Song of the humpback whale-population comparisons. Behav. Ecol. Sociobiol. 8:41-46.
- Wolman, A. A. and C. M. Jurasz. 1977. Humpback whales in Hawaii: vessel census, 1976. Mar. Fish. Rev. 39(7):1-5.
- Wrangham, R. W. 1986. The evolution of social structure. In: Primate societies, B. B. Smuts, D. L. Cheney, R. M. Seyfarth, R. W. Wrangham and T. T. Struhsaker (eds.). University of Chicago Press, Chicago, Illinois.
- Wrangham, R. W. and D. J. Rubenstein. 1986. Social evolution in birds and mammals. In: Ecological aspects of social evolution: birds and mammals, D. I. Rubenstein and R. W. Wrangham (eds.). Princeton University Press, Princeton, New Jersey. pp:452-527.
- Wursig, B., Dorsey, E. M., Fraker, M. A., Payne, R. S. and J. W. Richardson. 1986. Behavior of the bowhead whales Balaena mysticetus, summering in the Beaufort Sea: a summary. Rep Int. Whal. Commn. Special Issue 8:167-205.

Yablokov, A. V. and L. S. Bogoslovskaya. 1984. A review of Russian research on the biology and commercial whaling of the gray whale. In: The gray whale <u>Eschrichtius robustus</u>, M. L. Jones, S. L. Swartz and J. S. Leatherwood (eds.). Academic Press, Inc., Orlando, Florida. pp:465-486.